

EVERYTHING
YOU NEED
TO CREATE
A SAFER
OUTDOORS

LANDSCAPE **PROTECTION**





Creating Better Spaces

ABOUT MARSHALLS

Marshalls is the UK's leading hard landscaping company. We have achieved this status through progressive product innovation and by demonstrating outstanding service levels to our customers. This privileged position will be sustained by continuous investment in our brand, our products, and our people.

Our vision is built on four pillars:

• DEMONSTRATING LEADERSHIP

We believe in driving the industry forward. It's an ambition we've been acting on for over 120 years, thanks to our size, capability, range of products and unmatched market knowledge.

DELIVERING EXCELLENCE

We have very high standards. Our products have to be innovative, our people have to be the best, our workmanship has to be perfect. Only then can we deliver the quality we're renowned for, at every stage of the process.

BUILDING TRUST

Everyone at Marshalls acts with integrity, treating customers and their projects with care and respect. It means people trust us with their home, their business, their town. And it's how we foster relationships for the long-term.

BEING SUSTAINABLE

We use the world to source our products, so we have a responsibility to look after it. It's something we have been committed to for over 120 years and has ensured our longevity. Whether it's creating stronger communities, preserving environments, or contributing to the UN Global Compact, our work is always sustainable.

Our environment impacts everything we do. The better our environment, the better we can be. At Marshalls our aim is to create opportunities for better spaces for all, in our homes, streets, schools, offices and retail spaces. The Marshalls product range is designed around inspiring others to imagine better and create exceptional landscapes for all to enjoy.

LANDSCAPE PROTECTION

Marshalls Landscape Protection offers a new approach – a design, engineering and specification philosophy that enables highly effective protection to blend seamlessly into urban landscape design; allowing architects, planners and designers to install the security measures without instilling fear.

Our developments in design, manufacture and technology negate the need for bulky and obtrusive security, enabling those who design our city spaces to think more creatively about how they can include Hostile Vehicle Mitigation within landscape design features.

Marshalls' integrated Landscape Protection approach involves the application of creative thinking, using our engineering and design know-how to create spaces that are safer by design from the outset.



Proudly celebrating our tenth year as a superbrand



























CONTENTS

	INTRODUCTION	
OF COR	Design & Engineering Capability	06
	Project Management	07
	Protective Solutions For All Environments	08
กักสักห 🚚	DEFEND	
COSTA IMAX PAIR	Legislations Explained	12
	International Standards Comparison	14
	Protective Bollards	16
	RhinoGuard® PAS170 Bollards	22
	Temporary Protection Solutions	24
THE PARTY OF THE P	Protective Street Furniture	26
	Automated Protective Products	4(
	Post and Rail	42
	Redi-Rock™ Modular Wall	44
	DEFLECT	
	Stainless Steel Bollards	4
	Mild Steel Bollards	5
	Ferrocast® Bollards	5
	Concrete Bollards	6
	Natural Stone Bollards	7
	Cast Iron Bollards	7
	Timber Bollards	7
	Plastic Bollards	7
	Telescopic Bollards	8

DETER

Engineering Capability	06	Street Furniture
lanagement	07	Natural Elements
e Solutions For All Environments	08	Affinité
		Citi Elements®
)		Stratic
ons Explained	12	Loci
onal Standards Comparison	14	GEO
e Bollards	16	Tramet
ard® PAS170 Bollards	22	Rendezvous
ry Protection Solutions	24	Metrolinia
e Street Furniture	26	Boxland
ed Protective Products	40	Tenplo
Rail	42	Marshalls M3
k™ Modular Wall	44	Festival
		ldylle
T		Waterside
Steel Bollards	48	Coda
l Bollards	52	Igneo
® Bollards	58	Demetra
Bollards	66	Urbain®
tone Bollards	70	
Bollards	72	
allarde	76	

DETER

86	Mobile Gardens	168
88	Planters	170
94	Seating	174
98	Tables	230
104	Litter Bins	236
108	Tree Grilles	246
114	Post and Rail	254
120	Traffic Calming	260
124	Kerb Systems	266
128		
134	CASE STUDIES	
136	Fosse Shopping Park	270
138	Leeds Flood Alleviation Scheme	272
142	Jaguar Land Rover	274
146	Elephant and Castle	276
148	Exhibition Road	278
152	Leicester Square	280
156	Alhambra Theatre	282
160	Leisure Plaza	284
	Th C. II	























Design & Engineering Capability

If you can't find what you need within the Marshalls Landscape Protection range, your options don't end there.

Our specialist design and engineering teams are experienced in a range of materials from natural stone and concrete to mild steel, stainless steel and timber.

Only by consistently pushing boundaries and challenging convention can we create public spaces that stand out.

Our exceptional bespoke products often start with a flash of inspiration that needs to be fully explored and carefully nurtured throughout the project.

With every element sourced, tailored or created around your project vision, our theoretical and practical understanding of urban space is unrivalled.

We love to stretch our creativity beyond the typical. Inspired by your vision, ambition and aspiration our open-minded approach means:

'We will where others won't.'









Bella Italia

Project Management

To ensure projects run smoothly, Marshalls follow a structured 7 step approach led by a dedicated Project Manager from the initial programme of works through to the site inspection and project handover.

PROJECT MANAGER ALLOCATED

A specialist project manager is allocated to the client giving a single point of contact from initial project scoping through to installation and handover.

PROVISIONAL PROGRAMME

Working alongside the client, the dedicated Project Manager will detail a provisional programme of works considering site conditions, site programme, contractual implications and health and safety.

SITE SURVEY

If a site survey is required, it will be conducted by a fully qualified member of the Marshalls team, following which the client will be provided with layout drawings for

DESIGN

Following layout approval, product specification drawings will be issued and prototype products can be provided within this stage for certain bespoke projects.

FINAL REVIEW

Product design and project time-frames are confirmed in preparation for commencement of works.

06 INSTALLATION

Installation conducted by a specialist Marshalls Landscape Protection install team working in collaboration with the Project Manager.

PROJECT HANDOVER AND O&M

Project Manager to lead a site inspection and final evaluation with the client.





DEFEND

The terror threat posed to the public has evolved dramatically over the last couple of years. Large-scale, meticulously planned bomb attacks have given way to vehicle assaults that target pedestrians.

There has also been an increased risk from errant vehicles whether that is through ram-raids, accidental collisions or texting behind the wheel.

Concrete blocks and barricades - largely temporary measures - have been installed across the UK to protect areas of high footfall, such as city centres, airports and sports stadiums.

We believe that those in charge of specifying for security must assign a greater role to design aesthetics when it comes to choosing products to prevent vehicle attacks.





Legislations Explained

Performance and Application

At the heart of Hostile Vehicle Mitigation is the BSI Publicly Available Specifications (PAS). Each standard enables the specification of assured protection against hostile vehicles.

PAS 68

The Publicly Available Specification, PAS 68, specifies a performance classification for vehicle security barriers and their foundations when subjected to a horizontal impact.

The standard was devised and administered by the Centre for the Protection of National Infrastructure (CPNI), and tests security barriers at varying speeds, using different size vehicles. Whilst it is only through specifying products successfully tested in accordance with PAS 68 that protective security can truly be assured, this does not necessarily mean that the highest specifications of PAS 68 protection are always required.

PAS 69

BSI PAS 68 is complemented by the PAS 69 document, which provides guidance on the selection, installation, foundations and use of PAS 68 tested security products, taking into account site specific conditions, to ensure they are placed as effectively as possible.

PAS 69 suggests a maximum gap of 1.2m between the installed, upright faces of successive security products, to ensure that vehicles are prevented from encroaching freely between the barriers.

			Vehicle Mass (kg)		
Vehicle Speed km/h (mph)	1.5 tonne Saloon Car (M1)	2.5 tonne 4x4 Pickup (N1G)	3.5 tonne Flatbed Van	Empty 18 tonne 2 Axle Lorry (Weighs 7.5 tonnes - N3)	30 tonne 4 Axle Lorry
16 (10)	15kJ	25kJ	35kJ	74kJ	296kJ
32 (20)	59kJ	99kJ	138kJ	296kJ	1185kJ
48 (30)	133kJ	222kJ	311kJ	667kJ	2667kJ
64 (40)	237kJ	395kJ	553kJ	1185kJ	4741kJ
80 (50)	370kJ	617kJ	864kJ	1852kJ	7407kJ
96 (60)	533kJ	889kJ	1244kJ		
112 (70)	726kJ	1210kJ			
-					

The table above provides the kinetic energy values (in kj) created on impact, for each of the vehicle types and speeds used in PAS 68 impact testing.

C-VAW

C-VAW testing is a government approved approach to proving a product's resistance from a ramming vehicle attack. Various vehicles are used to see how the system will perform from other attacks including angular and driving at gaps between the products

IWA 14.1

IWA 14.1 is an international standard for counter terrorism impact testing agreements which incorporates PAS 68, ASTM 2656, and the CEN Workshop Agreement.

Hence, no matter where you are based or where you want to create a safe and beautiful space, the IWA workshop agreement standardises all counter terrorism impact testing agreements and models and combines them into one, making the testing and specification of products easier and clearer for all specifiers.

IWA 14.2

IWA 14.2 provides guidance for the selection, installation and use of vehicle security barriers (VSBs) and describes the process of producing operational requirements (ORs).

IWA 14.2 also gives guidance on a design method for assessing the performance of a VSB.

PAS 170

PAS 170 delivers a testing standard for vehicles of up to 2.5 tonnes travelling at 10 or 20mph. Lower than the regulations developed to mitigate against vehicle born terror attacks.

Unlike previous anti-ram solutions, new products tested and certified by PAS 170 provides businesses and local authorities with assurance and proof of performance for the first time.

12

International Standards Comparison

Over the last 15 years the Hostile Vehicle Mitigation testing standards have progressed from just one to a few being adopted around the world. The table below shows comparisons between the USA and international testing standards. For further information please contact the Marshalls Landscape Protection team.

Vehicle	Vehicle	Vehicle Weight in KG, IWA/USA (ASTM vehicle class)									
Speed (kph)	Speed (mph)	1500/ 1100 (C)	2500/ 2300 (P)	3500	7200 N2	7500 N3/ 6800 (M)	Old USA K Rating	30000/ 29500 (H)			
		Energy in Kj									
16	10	15	25	35	71	74		296			
32	20	59	99	138	284	296		1185			
48	30	133	222	311	640	667/656	K4	2667/2850			
64	40	237/179	395/375	553	1138	1185/1110	K8	4741/4810			
80	50	370/271	617/568	864	1778	1852/1680	K12	7407/7283			
96	60	533/424	889/887	1244							
112	70	726	1210								

(International/USA)



The UK IWA14.1, PAS 68 and USA ASTM2656 standards use a similar array of vehicles and speeds for testing and therefore deliver similar energy in terms of kilojoules. The following table shows the differences between the standards due to the weight of the vehicles being used that are appropriate to the locally available vehicle types. PAS 68 has developed into the current IWA14.1 and ASTM has grown from the original USA K ratings standard.

UK IWA 14.1 Classification

Performance rating = IWA 14–1: Anon Bollard V/7200[N3C]/48/90:2.6

Parameter	Rating	Explanation
VSB	Bollard	Product type
Test type	V	Vehicle impact test
Test vehicle mass	7 200	7 200 kg
Vehicle classification	N3C	2 axle rigid
Impact speed	48	48 km/h
Impact angle	90°	90° respectively to the impact face of the VSB
Vehicle penetration distance	2.6	the test vehicle penetrated 2.6 m beyond the VSB datum line

USA ASTM 2656 Classification

Performance Rating = M 50 P1

Parameter	Rating	Explanation
Vehicle Classification	М	Medium duty truck of 6800kg
Impact Speed	50	50 mph/ 80 kph
Vehicle Penetration	P1	Less than 1 metre



Protective Bollards

RhinoGuard® Product Options

Our RhinoGuard® range of bollards have a wide selection of sleeve options, various fixing types and foundation depths available to suit your scheme. All our cores have been tested from 1.5 tonnes to 7.5 tonnes at various speeds up to 50mph.

CORE RATING

The RhinoGuard® range has been designed to fulfil your aesthetic and security needs.


		Core Rating							
		15/30	25/40	35/30	72/40	72/50	75/30	75/40	75/50
	Steel	✓	✓	✓	✓	✓	✓	✓	✓
ptions	Stainless Steel	✓	✓	✓	✓	✓	✓	✓	✓
	Geo Stainless Steel	✓	✓	✓	✓	✓	✓	✓	✓
0	LED Marker	✓	✓	✓	✓	✓	✓	✓	✓
Sleeve	Decorative Sleeve	✓	✓	✓	✓	✓	✓	✓	✓
S	Ferrocast®	✓	✓	✓	✓	✓	✓	✓	✓
	Telescopic (foundation type)			✓					
Dimensions	Core Diameter (mm)	114	168	204	194	244	194	168 & 244	194 & 244
Dimer	Visible Height (mm)	1000	1000	1000	1000	1000	1000	1000	1000
urity	Test Standard	PAS68	PAS68	IWA 14.1	IWA14.1	IWA 14.1	PAS68	PAS68	PAS68:2010 PAS68:2013
Security	Vehicle speed (mph) / weight (kg)	1500/30	2500/40	3500/30	7200/40	7200/50	7500/30	7500/40	7500/50



RHINOGUARD® FOUNDATION TYPE

The RhinoGuard® bollard range comes with an option of foundation types, including the brand new Super Shallow which requires only 100mm depth.

(Please note not all products are available with each foundation, speak to a member of our team for more information)



			Core Rating							
		15/30	25/40	35/30	72/40	72/50	75/30	75/40	75/50	
on type	Super Shallow				✓					
	Shallow Mount		✓			✓	✓	✓		
	Shallow Mount Removable				✓	✓	✓	✓		
Foundation	Removable Reinforced Concrete Cage	✓	✓	✓				✓	✓	
Fc	Reinforced Concrete Cage	✓	✓	✓				✓	✓	
	Lift Assist			√						

RhinoGuard® Protective Sleeves



Height (mm)	1000	Height (mm)	1000	Height (mm)	1000	Height (r
Diameters (mm)	168, 194, 204, 273	Diameters (mm)	129, 154, 204, 256	Diameters (mm)	140, 204, 254	Diameter
Security rating options	Up to 75/50	Security rating options	Up to 75/50	Security rating options	Up to 75/50	Security options



1100

140, 204, 254

Up to 75/50



DECORATIVE SLEEVESvarious materials / finishes





Diameters (mm)	204, 254	Diameters (mm)	Assorted sizes	Diameters (mm)	139 PPC 154 Stainless Stee
Security rating options	Up to 75/50	Security rating options	Up to 75/50	Security rating options	35/30



Decorative sleeve options

Some of our sleeve options:

DIAMOND FADE







Finishes: Anthracite Grey RAL 7016 (RT-8286-I) Grey Aluminium

your custom

Speak to us about requirements!


DIAMOND FADE - MODERN • MODERN 2 • ORGANIC • STAINLESS

DUBAI - MODERN • MODERN 2 • ORGANIC • STAINLESS

Aluminium + RAL 7016 Anthracite Aluminium + RAL 7016 Anthracite Grey + RAL 9007 Grey Aluminium RAL 9007 Grey Aluminium















Dubai 254 - RAL 7016 Anthracite

FLOWER BURST - MODERN • MODERN 2 • ORGANIC • STAINLESS





Dubai 254 - Wildlife Sanctuary Top (RT-9909-XW) + Bronze

Grey Aluminium + RAL 9007 Grey Anthracite Grey + RAL 9007 Grey 8102-1) + Corten (RT-8286-I)

Dubai 254 - Corten (RT-8286-I) +





8286-I) + Bronze (RT-8102-1)

Corten Fossil Base (RT-1553)



Dubai 254 - Stainless Steel + RAL 9007 Grey Aluminium Fossil Base (RT-1553)

+ RAL 9007 Grey Aluminium + Bronze (RT-8102-1







A Diamond Fade - RAL 9007 Grey Aluminium + RAL 7016 Anthracite Grey **B** Diamond Fade - RAL 5011 Steel Blue + RAL 9007 Grey Aluminium C Diamond Fade - Corten (RT-8286-I) + Bronze (RT-8102-1)

D Diamond Fade - Stainless Steel + RAL 5011 Steel Blue

A Dubai - Stainless Steel + RAL 9007 Grey Aluminium **B** Dubai - Stainless Steel + RAL 5011 Steel Blue C Dubai - Stainless Steel + Corten Fossil Base (RT-1553

D Dubai - Stainless Steel + Bronze (RT-8102-1)






- A Flower Burst Stainless Steel + RAL 9007 Grey Aluminium
- **B** Flower Burst Stainless Steel + RAL 5011 Steel Blue
- **C** Flower Burst Stainless Steel + Corten Fossil Base (RT-1553)
 D Flower Burst - Stainless Steel + RAL 7016 Anthracite Grey

RhinoGuard® PAS170 bollards

PAS170 delivers a testing standard for vehicles up to 2.5 tonnes travelling between 10mph and 20mph. The Marshalls RhinoGuard®, successfully crash tested, PAS170 solutions provide assurance against lower speed ram-raids and impacts.



Name	Core diameter (mm)	Material	Finish	Foun- dation width (mm)	Height above ground (mm)	Foun- dation depth (mm)	Core weight (kg)
RHINOGUARD® PAS170 25/10	75	Mild Steel	Galvanised	700	800	200	45
RHINOGUARD® PAS170 25/10	75	Mild Steel	Gavanised & Powder Coated	700	800	200	45
RHINOGUARD® PAS170 25/20	139	Mild Steel	Galvanised	700	800	200	55
RHINOGUARD® PAS170 25/20	139	Mild Steel	Gavanised & Powder Coated	700	800	200	55


Mild Steel and Stainless Steel bollard sleeves are available with single or double reflective tape options.



Diameter (mm) 114 Diameter (mm) 100 Diameter (mm) 101 Diameter (mm) 101 Diameter (mm) 101 Diameter (mm) 101 Diameter (mm) 100 Diameter (mm) 100 Diameter (mm) 100 Diameter (mm) 154 Diameter (mm) 154 Diameter (mm) 154 Diameter (mm) 100 Diameter (mm) 154 Diameter (mm) 100 Diameter (mm) 100										
Sleeve weight (kg) 15 Overall weight (kg) 57 Diameter (mm) 168 Sleeve weight (kg) 6 Overall weight (kg) 48 Diameter (mm) 154				Diameter (mm)	114				Diameter (mm)	101
Overall weight (kg) 57 Diameter (mm) 168 Diameter (mm) 154 Diameter (mm) 154			/10	Height* (mm)	1000			25/10	Height* (mm)	1000
Diameter (mm) 168 g Diameter (mm) 154	1	g	25/	Sleeve weight (kg)	15		g		Sleeve weight (kg)	6
Diameter (mm) 168 g Diameter (mm) 154	4	\atin		Overall weight (kg)	57		Core Ratin		Overall weight (kg)	48
	П			Diameter (mm)	168				Diameter (mm)	154
	1		/20	Height* (mm)	1000			C 25/20	Height* (mm)	1000
Sleeve weight (kg) 23 Sleeve weight (kg) 9			25,	Sleeve weight (kg)	23				Sleeve weight (kg)	9
Overall weight (kg) 76 Overall weight (kg) 62				Overall weight (kg)	76				Overall weight (kg)	62

^{*} Height on all bollards denotes the visible height above ground

GEO STAINESS STEEL SLEEVESBead Blasted with Polished Top Cap



MANCHESTER FERROCAST® **SLEEVE**Painted – Standard RAL colours available



		Diameter (mm)	102				Diameter (mm)	225
	25/10	Height* (mm)	1100		ore Rating	25/10	Height* (mm)	1100
ص ا	25/	Sleeve weight (kg)	9	Core Rating			Sleeve weight (kg)	21
Rating		Overall weight (kg)	51				Overall weight (kg)	63
Core		Diameter (mm)	204				Diameter (mm)	350
	25/20	Height* (mm)	1100		720	Height* (mm)	1100	
	25/	Sleeve weight (kg)	16		25/	Sleeve weight (kg)	47	
		Overall weight (kg)	69				Overall weight (kg)	100

^{*} Height on all bollards denotes the visible height above ground




Temporary Protection Solutions

Marshalls RhinoGuard® GateKeeper™

The RhinoGuard® GateKeeper™ range provides temporary protective measures for a number of applications such as Christmas markets or sporting events.


The steel variation has been successfully crash tested to IWA 14.1, providing protection against vehicles up to 2.5 tonnes travelling up to 30mph. The tested solution is pedestrian permeable, with vehicle access points and requires no anchorage in any form and can be quickly deployed across all surfaces without relying on kerbs or structural aids.

The pedestrian permeable concrete GateKeeper[™] has been successfully tested to government approved C-VAW standards, which provides proven resistance from ramming vehicles. During the test, different vehicles were used to demonstrate how the GateKeeper[™] system would perform under various attack angles.



MARSHALLS RHINOGUARD® GATEKEEPER™

Stee




Material	Galvanised Steel
Colour Options	Standard RAL colours
Finish	Natural or powder coated
Shape	Rectangular
Shroud H x L x W (mm)	1000 x 1292 x 164
Shroud weight (kg)	30
Individual base unit H x L x W (mm)	90 x 1876 x 1763
Individual base unit weight (kg)	151
Test rating	25/30


MARSHALLS RHINOGUARD® GATEKEEPER™

Concrete





Height (mm)	1000
Length (mm)	1200
Width (mm)	600
Weight (kg)	1981
Finish	Raw grey concrete
Test rating	C-VAW










DEFEND

Protective Street Furniture









RhinoGuard® EOS 75/30 Seat

Protective Street Furniture



















RhinoGuard® 72/40 Blok

MATERIALS/COLOURS

Concrete





Timber





вьок		TIMBER CLAD		SEAT		BENCH	
Height above ground (mm)	580	Height above ground (mm)	625	Height above ground (mm)	970	Height above ground (mm)	625
Length (mm)	1600	Length (mm)	1600	Length (mm)	1600	Length (mm)	1600
Width (mm)	1000	Width (mm)	1100	Width (mm)	1100	Width (mm)	1100
Foundations (mm)	2120 x 1520 x 200	Foundations (mm)	2120 x 1520 x 200	Foundations (mm)	2120 x 1520 x 200	Foundations (mm)	2120 x 1520 x 200
Weight (kg)	2500	Weight (kg)	100 (top) 2500 (Concrete)	Weight (kg)	130 (Top) 2500 (Concrete)	Weight (kg)	130 (Top) 2500 (Concrete)

Protective Street Furniture

RhinoGuard® Giove 75/50 Planter



MATERIALS/COLOURS

Precious Stone











	V
Verde	N

ight above ground (mm)	1090	
dth (mm)	2000	
undation depth (mm)	950	
ot depth (mm)	300	


RHINOGUARD® TIMBER PLANTER





RHINOGUARD® STEEL PLANTER





Height above ground (mm)	1000	
Width (mm)	1200	
Length (mm)	1200	

Protective Street Furniture

RhinoGuard® Rectangle Planter




RHINOGUARD® SQUARE PLANTER Concrete

eight above ground nm)	950	Height above ground (mm)	1000
ngth (mm)	1800	Length (mm)	1100
idth (mm)	700	Width (mm)	1100
curity rating	up to 75/50	Security rating	up to 7











Height above ground (mm)	1100
Foundation root depth (mm)	500
Surface finishing (mm)	100
Overall length (mm)	1700
Overall width (mm)	1132
Core diameter (mm)	168
Sleeve diameter (mm)	204
Security rating	up to 75/50

Height above ground (mm)	850
Width x Length/ø (mm)	1900
Materials	Sandblasted precious stone concrete
Weight (kg)	2360
Security rating	Up to 72/50

Protective Street Furniture: Engineered Solutions



CRISTINA



GIOVE SMALL



Height above ground (mm)	880
Width x Length/ø (mm)	2500
Materials	Precious stone or white granite
Weight (kg)	3550
Security rating	Up to 72/50

Height above ground (mm)	600	Height above ground (mm)	735
Width x Length/ø (mm)	820 x 2000	Width x Length/ø (mm)	1500
Materials	Reinforced precious stone concrete	Materials	Marble stone or white granite
Security rating	Up to 72/40	Security rating	Up to 72/40

ORIONE



PEGASO



Height above ground (mm)	816
Width x Length/ø (mm)	520
Materials	Marble stone or white granite
Weight (kg)	242
Security rating	Up to 72/40

Height above ground (mm)	912
Width x Length/ø (mm)	640
Materials	Marble stone or white granite
Weight (kg)	374
Security rating	Up to 72/40



Protective Street Furniture: Engineered Solutions

SATURNO



ESILE



CLASSICA 1220



Height above ground (mm)	1200
Width x Length/ø (mm)	1500
Materials	Precious stone or white granite
Weight (kg)	2393
Security rating	Up to 72/50


Height above ground (mm)	900
Width x Length/ø (mm)	667
Materials	Reinforced precious stone concrete
Weight (kg)	297
Security rating	Up to 72/40

	Height above ground (mm)	650		
	Width x Length/ø (mm)	1220		
	Materials	Reinforced precious stone concrete		
	Weight (kg)	910		
	Security rating	Up to 72/40		

CLASSICA 1620



Height above ground (mm)	650
Width x Length/ø (mm)	1620
Materials	Reinforced precious stone concrete
Weight (kg)	1468
Security rating	Up to 72/40



Automated Protective Products

AUTOMATED BOLLARDS



Max 100

Root fixed

75/30, 75/40, 75/50

MATERIALS/COLOURS



RAL colours

Options











AUTOMATED BLOCKERS

AUTOMATED GATES



Max 1100

Max 4000

Root fixed

75/30, 75/40, 75/50

Height (mm)

Width (mm)

Std fixing type

Security rating

2400 Height (mm) Width (mm) 4200 Std fixing type Root fixed Security rating 75/40, 75/50

Heights and widths vary dependent on rating options. Other options available, please speak to a member of our team about your automated product requirements.

RhinoGuard® Titan® Kerb

The RhinoGuard® Titan® Kerb has been crash tested to IWA14.1 at a shallow angle and successfully deflects a vehicle traveling up to 80kph. The Titan® Kerb is is ideal for applications that require a product that does not affect the overall aesthetic of an area.



	External Radius								Internal Radius					
Height (mm)	400	400	400	400	400	400	400	400	400	400	400	400	400	400
Face Length (mm)	965/975	955/975	945/975	935/975	797/841	734/785	807/884	317/394	217/294	975/955	975/935	836/785	961/884	589/666
Width (mm)	390	390	390	390	390	390	390	390	390	390	390	390	390	390
Radius Covered (m)	76/25	25/15	15/11	11/8.5	7.5	6.0	4.5	2.0	1.5	76/25	76/25	76/25	76/25	76/25
No per 1/4 circle	122-40	40-24	24-18	18-14	14	12	8	8	8	122-40	122-40	122-40	122-40	122-40
Weight (kg)	233	232	230	229	207	194	221	104	80	232	229	182	198	132

Height (mm)

Std fixing type


Security rating

Base diameter (mm) | Max 350

Post & Rail

Marshalls Landscape Protection offers a range of protective post and rail systems which are available in a range of styles and materials. Speak to our experts for more information.

		Core Rating							
		15/30	25/40	35/30	72/40	72/50	75/30	75/40	75/50
	Stainless Steel	✓	✓	✓	✓	✓	✓	✓	✓
Product	Mild Steel	✓	✓	✓	✓	✓	✓	✓	✓
Proc	Geo	✓	✓	√	✓	✓	✓	✓	✓
	DecorGuard	√	√	√	√	√	√	✓	✓
	Security rating	PAS68	PAS68	IWA14.1	IWA14.1	IWA14.1	PAS68	PAS68	PAS68
	Vehicle weight/ speed (kg/mph)	1500/30	2500/40	3500/30	7200/40	7200/50	7500/30	7500/40	7500/50





Height (mm)	1000
Base diameter	various based on rating requirements
Standard Fixing	Root Fixed
Security rating	Upto 75/50
* 11 . 1	

	Height (mm)	1000
sed nts	Base diameter	various based on rating requirements
	Standard Fixing	Root Fixed
)	Security rating	Upto 75/50

Height (mm)	1000	
Base diameter	various based on rating requirements	
Standard Fixing	Root Fixed	
Security rating	Upto 75/50	

Height (mm)	1040
Base diameter	various based on rating requirements
Standard Fixing	Root Fixed
Security rating	Upto 75/50

Redi-Rock™ Modular Wall

Redi-Rock™ hostile vehicle mitigation walling (Vehicle Security Barriers- VSB) is proven to stop a 7.5 tonne truck at 48km/h (30mph) and is an effective, re-usable solution to hostile vehicle attack that requires minimal maintenance.

The force protection system of Redi-Rock™ blocks are interconnected with steel cables and have been successfully tested by the Transport Research Laboratory (TRL) using the BSi specification PAS 68:2007 and achieved a classification of V/7500(N2)/48/90:1.6/0.0.

With no ground anchors required, the fast-to-install freestanding blocks can be deployed, picked up and moved with no ground work required; this makes it ideal for use in crowded places, transport hubs, utility and critical infrastructure as well as buildings of high importance.

Due to its natural stone appearance Redi-Rock™ blends into the background and protects without looking out of place.

Benefits of Redi-Rock™

- Fast to install
- Removable/relocatable
- No ground anchors required as it uses its own weight
- Integral cable dissipates kinetic energy
- Aesthetically pleasing, blends into surrounding
- Can create a safe working area for everyone, including your workforce
- Provides security against hostile and accidental vehicle attack
- Helps to direct traffic from problematic areas



SECURITY RATING

2007 V/7500(N2)/48/90:1.6/0.0

PAS 68:

	v · · ·	
Height (mm)	Variable	
Std fixing type	Freestanding	
Colour options	Limestone Cobblestone Ledgestone	
Security rating	75/30	

FINISH / COLOUR

DESIGN OPTIONS

Available in the following finishes:










The Redi-Rock™ system is also available as a standard walling system for the retention of earth, landscaping and flood protection applications. For more information on this system please contact a member of the team.







DEFLECT

DEFLECT

Marshalls' Landscape Protection bollards provide an assurance of protection in any space. Marshalls provides a range products that provide safety and restriction to public spaces without compromising the aesthetics of the landscape.

Our bollards provide the opportunity to offer direct security to any space. Available in a wide choice of styles and material options, our bollard range offers customers an almost unrivalled choice that will suit almost any application. Combine and coordinate with our wide range of Street Furniture to add character to any space.

Our bollard ranges are available in crash tested and non-crash tested versions depending on the level of security and protection required.



Stainless Steel Bollards

Marshalls' Landscape Protection stainless steel bollards are exceptionally strong and require little maintenance. They are suitable for a variety of applications, such as providing protected parking as well as safety for pedestrian walkways.

DESIGN OPTIONS

FINISH / COLOUR

All stainless steel bollards are supplied with a brushed satin finish as standard, with the exception of RS007 which has





Brushed

Polished -RS007 Bollard Only

BESPOKE BRANDING

Rhino bollards are also available with the option of bespoke branding machine engraved into the top, giving you the option to fully customise your scheme with a logo or crest. Branding can be supplied unpainted or full colour.





REFLECTIVE BANDING OPTIONS



Single Band

Reflective Banding Rhino bollards are available with reflective banding for increased visibility and safety. Banding is available in a choice of 3 standard colours – amber, red and white.

BEZEL



All stainless steel bollards are available with a brushed satin bezel for use in applications where bollards are installed into existing paving, ensuring that any gaps around the bollard base are hidden from view.

FIXING TYPES & FOUNDATION DEPTHS:



Surface Mount




















Stainless Steel Bollards




Height (mm)	1000
Diameters (mm)	101, 114, 129, 154
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable

Height (mm)	1000	
Diameters (mm)	114	
Std fixing type	Root fixed	
Optional fixing types	Surface mounted Removable	

Height (mm)	1000
Diameters (mm)	101, 114, 129, 154
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable

Height (mm)	1000
Diameters (mm)	114
Std fixing type	Root fixed
Optional fixing types	Removable



Mild Steel Bollards

Marshalls' range of Rhino steel bollards provides strong, simple and cost effective security measures ideal for access control, ram raiding deterrence and creation of pedestrian walkways. Each Rhino steel bollard has a number of options to enable you to customise products to suit your scheme.

DESIGN OPTIONS


FINISH / COLOUR

RAL colour





















Surface Mount

BESPOKE BRANDING

Rhino bollards are also available with the option of bespoke branding machine engraved into the top, giving you the option to fully customise your scheme with a logo or crest. Branding can be supplied unpainted or full colour.






















Mild Steel Bollards



Height (mm)	1100	
Width x depth (mm)	140 x 80	
Std fixing type	Root fixed	
Optional fixing types	Surface fixed	

Height (mm)	1000	
Width x depth (mm)	140 x 90	
Std fixing type	Base plated	
Options	LED panel illumination	

Height (mm)	1000
Diameters (mm)	114, 139, 168, 194
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable

Height (mm)	1000
Diameters (mm)	114, 139, 168, 194
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable



Removable

Mild Steel Bollards



Height (mm)	1000	
Diameters (mm)	114, 139, 168, 194	
Std fixing type	Root fixed	
Optional fixing types	Surface mounted Removable	

Height (mm) 1000 Diameters (mm) 114, 139, 168, 194
Diameters (mm) 114, 139, 168, 194
Std fixing type Root fixed
Optional fixing Surface mounted kemovable

Height (mm)	1000
Diameters (mm)	140
Std fixing type	Root fixed
Optional fixing types	Removable

Height (mm)	1000
Diameters (mm)	114, 139, 168, 194
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable



Ferrocast® bollards are an ideal way to increase security around your perimeter. Suitable for use in almost any situation and available in a number of styles to coordinate with most landscapes, whether traditional or contemporary.

DESIGN OPTIONS

FINISH / COLOUR

RAL colour





















BANDING OPTIONS

- ☑ Reflective Tape
- Ballotini Reflective Beads
- ☑ Hand Painted Gold

BESPOKE BRANDING

Rhino bollards are also available with the option of bespoke branding, giving you the option to fully customise your scheme with a logo or crest. Branding can be supplied unpainted or in full colour.



SIGNAGE



FIXING TYPES & FOUNDATION DEPTHS:



Removable









Height (mm)	1000
Base diameter (mm)	225
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable

Height (mm)	895
Base diameter (mm)	160
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable

Height (mm)	970
Base diameter (mm)	155
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable

Height (mm)	900
Base diameter (mm)	150
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable





Height (mm)	917
Base diameter (mm)	175
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable

Height (mm)	915
Base diameter (mm)	168
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable

Height (mm)	1000	Height (mm)
Base diameter (mm)	168	Base diameter (mm)
Std fixing type	Root fixed	Std fixing type
Optional fixing types	Surface mounted Removable	Optional fixing types

Height (mm)	1000, 900
Base diameter (mm)	125
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable




Height (mm)	950
Base diameter (mm)	145
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable

Height (mm)	1127	
Base diameter (mm)	165	
Std fixing type	Root fixed	
Optional fixing types	Surface mounted Removable	

Height (mm)	1098
Base diameter (mm)	124
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable

Height (mm)	896
Base diameter (mm)	157
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable





DEANSGATE



DIXON ANTI-RAM

Height (mm)	983
Base diameter (mm)	130
Std fixing type	Root fixed
Optional fixing types	Surface mounted Removable

Height (mm)	1000
Base diameter (mm)	175
Std fixing type	Root fixed
Optional fixing types	Removable

t (mm)	1140	Height (mm)	1000
iameter (mm)	115	D !:	155
		Base diameter (mm)	155
ing type	Root fixed		
nal fixing	Removable	Std fixing type	Root fixed



Height (mm)	1000	
Base diameter (mm)	220	
Std fixing type	Root fixed	
Optional fixing types	n/a	

Height (mm)	1000	
Base diameter (mm)	220	
Std fixing type	Root fixed	
Optional fixing types	n/a	

Height (mm)	1000
Base diameter (mm)	110
Std fixing type	Root fixed
Optional fixing types	Removable


Height (mm)	3000
Base diameter (mm)	173
Std fixing type	Root fixed



Concrete Bollards

Our comprehensive range of concrete bollards contains numerous designs and finishes, encompassing the purely utilitarian and those with contemporary styling, providing choices for a range of different environments.

FIXING TYPES & FOUNDATION DEPTHS:



DESIGN OPTIONS

FINISH / COLOUR























REFLECTIVE BANDING OPTIONS









Optional fixing

Concrete Bollards








Optional fixing

Natural Stone Bollards

Marshalls' natural stone bollards are functional and create clean and simple solutions for any urban space. The range uses high quality granite, one of the hardest stones which can be used to create bollards that are strong, durable and enduring.

DESIGN OPTIONS



FIXING TYPES & FOUNDATION DEPTHS:



Natural Stone Bollards



Height above ground (mm)	579
Base width (mm)	300
Std fixing type	Surface mounted
Options	Available in Silver Grey, Black or Mid Grey Polished or Fine Picked finish

Height above ground (mm)	822
Base width (mm)	400
Std fixing type	Surface mounted
Options	Available in Silve Grey, Black or Mid Grey Polished or Fine Picked finish

Height above ground (mm)	1000
Foundation depth (mm)	300
Std fixing type	Root fixed
Options	Available in Silver Grey, Black or Mid Grey Polished or Fine Picked finish

Height above ground (mm)	550
Foundation depth (mm)	40
Std fixing type	Root fixed
Options	Available in Silver Grey, Black or Mid Grey Polished or Fine Picked finish

Cast Iron Bollards

Marshalls offer a range of traditional and contemporary cast iron bollards to help protect the landscape.

DESIGN OPTIONS

FINISH / COLOUR

Wet painted RAL 9005 as standard



Jet Black RAL 9005

Speak to us about other colour options









IMPERIAL MSF 114




Cast Iron Bollards









Height above ground (mm)	1000	
Base diameter (mm)	240	
Std fixing type	Root fixed	

Height above ground (mm)	1000	
Base diameter (mm)	330	
Std fixing type	Root fixed	

Height above ground (mm)	1000
Base diameter (mm)	345
Std fixing type	Root fixed

Height above ground (mm)	1000
Base diameter (m	m) 400
Std fixing type	Root fixed

ANTONY GORMLEY No4



Timber Bollards

Bring natural materials into an urban environment with the use of Marshalls timber bollards. With a choice of styles and timber types the bollards are suited to a range of different applications and budget requirements.


DESIGN OPTIONS

FINISH / COLOUR



Natural Finish

FIXING TYPES & FOUNDATION DEPTHS:




REFLECTIVE BANDING OPTIONS



Single band



OLLERTON - TIMBER SQUARE CHAMFERED TOP



OLLER	TON -	TIMB	ER
OUND	CIRCU	JLAR	TOP



Height above ground (mm)	1000	Height above ground (mm)	1000
Base diameter (mm)	125	Base diameter (mm)	150
Std fixing type	Root fixed	Std fixing type	Root fixed
* both also available in 125	150 200 and 250 di	 _	





Plastic Bollards


Marshalls' range of plastic bollards are an ideal solution for use in multiple locations. Plastic bollards are low maintenance, durable and long lasting.

DESIGN OPTIONS

FINISH / COLOUR



FIXING TYPES & FOUNDATION DEPTHS:





SUPERMARKET BOLLARD

HERITAGE 150



Height above ground (mm)	1000
Base diameter (mm)	125
Std fixing type	Root fixed
Optional fixing types	Surface mount, Removable, Anti-ram

Height above ground (mm)	1024
Base diameter (mm)	171
Std fixing type	Root fixed
Optional fixing types	Surface mount, Removable

SENTINEL 150

SENTINEL 150 VISIBOL



SENTINEL DECORATIVE



Height above ground (mm)	1024
Base diameter (mm)	166
Std fixing type	Root fixed
Optional fixing types	Surface mount, Removable

Height above ground (mm)	1024
Base diameter (mm)	166
Std fixing type	Root fixed
Optional fixing types	Surface mount, Removable

Height above ground (mm)	926	
Base diameter (mm)	166	
Std fixing type	Root fixed	
Optional fixing types	Surface mount, Removable	



Telescopic Bollards

Rhino Telescopic Bollards provide **DESIGN OPTIONS** a secure, simple and cost effective access control method of protecting premises and vehicles for domestic and commercial applications. Fully retractable, the bollards can be lifted out of the ground in seconds and lowered just as easily.

Galvanised



Galvinised Stainless

RAL 9010







Gentian Blue RAL

Traffic Red RAL 3020

FINISH / COLOUR





Single Band

Reflective Banding

Moss Green Traffic RAL 6005 Yellow RAL 1023



Double Band

Rhino bollards are available with reflective banding for increased visibility and safety. Banding is available in a choice of 3 standard colours – amber, red and white.

FIXING TYPES & FOUNDATION DEPTHS:

REFLECTIVE BANDING OPTIONS

RT R14 STAINLESS STEEL



Height (mm)	850 or 670
Diameter (mm)	114
Std fixing type	Telescopic

RHINO RD4 SS



RHINO RT RD4



RHINO RT KEY OP FOLD DOWN



RHINO RT SS



	Height (mm)	500
	Diameter (mm)	76
	Std fixing type	Telescopic

Height (mm)	500
Diameter (mm)	76
Std fixing type	Telescopic

Height (mm)	650	
Diameter (mm)	60	
Std fixing type	Surface mount	

Height (mm)	710	ı
Diameter (mm)	101	ı
Std fixing type	Telescopic	ı







Height (mm)

Std fixing type

Base diameter (mm) 90



RHINO RT 114 HD



Height (mm)

Std fixing type

Base diameter (mm) 114

Telescopic

RHINO RT R14 HD



	Height (mm)	850
	Base diameter (mm)	114
	Std fixing type	Telescopic

RHINO RT SU5



	Height (mm)	730
	Base diameter (mm)	135
	Std fixing type	Telescopic



Height (mm)

Std fixing type

Base diameter (mm) 90

Telescopic

DETER


Marshalls' Landscape Protection products offer the perfect solution for a large range of environments where a deterrent solution is required. The product range offers a number of flexible solutions that are suitable for a wide range of applications.

The deter product range consists of Street Furniture, either as individual pieces or ranges, post & rail systems or traffic calming measures.

Our ranges offer flexible solutions to suit any style of project and scheme.
















The Natural Elements Collection, inspired by biophilic design, is a modular based Landscape Furniture range that aims to introduce natural materials into urban spaces where people can sit and wellbeing is improved.







Personalised configurations are available with playful modules

STEP 1 Start with end panel

Select an end panel with or without arms. Option to illuminate panel.





Select your core modules

Modules can be configured in any sequence. Option to add low level lighting along the length of core modules.

STEP 2

STEP 4

Select transition modules

Choice of modules to go around corners at 45° or 60° angles. Further core components can be added as required. Repeat

to change direction

step 2 if creating longer configurations.

STEP 5

Finish with end panel

Please see step 1

STEP 6

Ancillary elements

Ancillary elements such as a litter bin, bollard or cycle stand are also available to maintain the design language.

Standalone seat and bench also available.





UNLIMITED FLEXIBILITY

Mix and match from the selection of playful components to create unlimited configurations.

With Natural Elements



A. END PANEL

L - 500 mm, H - 470 mm, W - 75 mm

B. END PANEL WITH ARMREST

L - 500 mm, H - 670 mm, W - 75 mm

panel as standard. C. ARMREST

Non lit end panels,

planters, transition modules and bollards will

have a galvanised and

powder coated laser cut

L - 500 mm, H - 700 mm, W - 70 mm

STEP 3

if required.

Select an armrest

Choose armrest option between units

System components: Create your seating solution using the components below

























1. SEAT MODULE

L - 1640 mm, H - 899 mm, W - 500 mm

2. CONCAVE BENCH MODULE

L - 1640 mm, H - 450 - 500 mm, W - 500mm

3. 45° RADIUS CORNER

L - 881 mm, H - 500 mm, W - 500 mm

4. CONVEX BENCH MODULE

L - 1640 mm, H - 500 - 550 mm, W - 500 mm

5. PLANTER MODULE

L - 1200 mm, H - 500 mm, W - 500 mm

6. 60° RADIUS CORNER

L - 570 mm, H - 500 mm, W - 468 mm

7. CYCLE STAND

L - 70 mm, H - 700 mm, W - 500 mm

8. BOLLARD

L - 140 mm, H - 1000 mm, W - 90 mm

9. SEAT WITH ARMS

L - 1790 mm, H - 899 mm, W - 500 mm

10. RECYCLE BIN

L - 600 mm, H - 1040 mm, W - 480 mm

11. PLANTER

L - 1350 mm, H - 500 mm, W - 500 mm

12. CONCAVE BENCH

L - 1790 mm, H - 450 - 500 mm, W - 500 mm

Natural Elements Collection

The form and design style of the modular range resembles patterns found in the natural environment and the FSC®-certified timber is responsibly sourced from well managed sources. The steel elements that help combine the modules are laser cut with a These are either available as side LED light panels or low level signature cell-like pattern to create a striking effect.

The range elements are clad with FSC®-certified redwood timber, available in a choice of two water based woodstains. Steel feature panels are finished in a choice of two patented powder coating systems giving the appearance of an aged material.

The collection also incorporates decorative integrated lighting to enhance the aesthetics of a scheme.

lighting incorporated into the base of the modules.



Look for our

FSC®-certified















AFFINITÉ


The Affinité seating range is an urban planning solution offering unlimited options to sculpt the urban landscape. Straight or curved models, aligned slats of wood, with or without backrests, free standing installation or combined installation. Lengths and shapes reflects your creativity. reflects your creativity.

Affinité lets you freely imagine whatever suits you in creating your public spaces to match their uses.










Affinité Collection









L - 1569 mm, H - 450 mm, W - 518 mm

2. CURVED THREE PLACE BENCH WITH BACKREST

L - 1569 mm, H - 766 mm, W - 564 mm

3. CURVED THREE PLACE BENCH WITH BACKREST

L - 1569 mm, H - 766 mm, W - 564 mm

4. WIDE THREE PLACE BENCH

L - 1800 mm, H - 450 mm, W - 674 mm


5. SLIM TWO PLACE BENCH

L - 1213 mm, H - 450 mm, W - 462 mm

6. SLIM THREE PLACE BENCH

L - 1800 mm, H - 450 mm, W - 462 mm





7. STOOL

L - 466 mm, H - 450 mm, W - 462 mm





The elegant design, the light lines, the discreet assembly of the Affinité modules will add a qualifying positive and elaborated image to your landscape.

The soft shape of the wooden slats will offer comfort and well being to the users.


Create your tree surrounds, curvy shapes, straight alignments or whatever you have an affinity for.

Available in FSC®-certified timber or non FSC®-certified timber.




































Citi Elements® is a collection of street furniture offered in a choice of materials and finishes providing customisation at affordable prices. The multi-material design means there is a configured solution to suit almost any landscape.





Citi Elements®













1. BENCH

L - 1820 mm, H - 475 mm, W - 416 mm

2. BENCH (END ARMS)

L - 1920 mm, H - 475 mm (635), W - 416 mm

3. BENCH (ALL ARMS)

L - 1920 mm, H - 475 mm (635), W - 416 mm

4. SEAT

L - 1820 mm, W - 524 mm, H - 814 mm

5. SEAT (END ARMS)

L - 1920 mm, W - 524 mm, H - 814 mm

6. SEAT (ALL ARMS)

L - 1920 mm, W - 524 mm, H - 814 mm

L - 1820 mm, W - 630mm, H - 750 mm

Citi Elements® Collection

Citi Elements* is an exciting new collection of street furniture offered in a choice of materials and finishes providing customisation at affordable prices. The multimaterial design means there is a configured solution to suit almost any landscape.

The eco-friendly materials, including 100% recycled plastic and FSC*-certified hardwood and softwood timber, help to protect the planet for future generations.



FSC www.fsc.org FSC* C133609

The mark of responsible forestry

















































4. SEAT

5. BENCH

L - 1800 mm, H - 800 mm

L - 1800 mm, H - 452 mm




H - 750 mm, W - 798 mm

2. ROOT FIXED CYCLE STAND

H - 1000* mm, W - 798 mm

3. ROOT FIXED CYCLE STAND WITH TAPPING BAR

H - 1000* mm, W - 798 mm



* Both fixing types have the same finished height of 750 mm with 250 mm of the root fix being below ground level





Essentials Collection

Essentials is a range of functional street furniture at great value prices offered in a choice of finishes. Available in 304 stainless steel with an option of powder coated steel or timber slats.

The design and materiality is the perfect choice for the demands of retail and business parks, car parks and walkways. Introducing seating spaces within public areas provides comfort and accessibility.































1. SEAT

L - 2012 mm, H - 767 mm, W - 450 mm

2. BENCH

L - 2012 mm, H - 637 mm, W - 450 mm

3. PLANTER

L - 1200 mm, H - 800 mm, W - 600 mm

4. CYCLE STAND

L - 324 mm, H - 637 mm, W - 140 mm

5. LED MARKER

L - 200 mm, H - 950 mm, W - 200 mm

6. LITTER BIN

L - 500 mm, H - 1100 mm, W - 450 mm

Recommended Colour Combinations





Stratic Collection

The Stratic Collection combines a modern and dynamic range of products that mimic the finishes, smooth lines and contours of the automotive industry. A combination of materials including Accoya timber, cast aluminium, stainless steel and steel, provides an extremely durable and low maintenance solution, offered in a choice of contemporary colour options.

Timber is finished with a water based woodstain. The seating elements and cycle stand are manufactured from sleek cast aluminium, the LED marker from stainless steel with the planter and litter bin from steel.














CUSTOMISE LOCI TO YOUR SCHEME

Integral to the blueprint of Loci is the ability to introduce distinctive colour to create exceptional elements of Landscape Furniture. Available in all RAL shades, (including Effect colours and the metallic range), there are endless combinations to define Loci exactly as you wish.

Colour is applied to Loci in an environmentally friendly way through a powder coated system that is Volatile Organic Compound and solvent free, which provides a robust and durable finish. The powder coated paint application process ensures minimal waste, with excess powder collected and reused, resulting in low wastage and therefore economical

BASE COLOUR

Choose from Graphite Grey or Telegrey 2 for the main body of the unit.

The light coloured ethically sourced Emeri timber provides a signature Scandinavian feel to the furniture

ACCENT COLOUR

TIMBER

Any of the legs can be customised with an accent colour to give Loci its vibrant personality.

Step 1: Select your items

Step 2: Select your base colour

Step 3: Select your accent colour
















The Loci cycle stand is fitted with timber inserts as standard to protect cycle frames from damage. To customise the cycle stand, the timber can also be exchanged for a powder coated steel insert.





LOCI Collection



1. BENCH

L - 1600 mm, H - 460 mm, W - 380 mm

2. TABLE

L - 1600 mm, H - 760 mm, W - 745 mm

3. SEAT

L - 1600 mm, H - 800 mm, W - 455 mm

4. SINGLE SEAT

L - 600 mm, H - 800 mm, W - 455 mm

5. STOOL

L - 600 mm, H - 590 mm, W - 380 mm

6. MONOLITH - *Other Monolith sizes also available

L - 600 mm, H - 2000 mm, D - 120 mm*

7. BOLLARD

L - 140 mm, H - 1100 mm, W - 80 mm

L - 525 mm, H - 1100 mm, D - 420 mm

9. CYCLE STAND

L - 500 mm, H - 800 mm, D - 50 mm

10. FINGERPOST

H - 3330 mm

11. LUMINAIRE

L - 544 mm, H - 179 mm, W - 242 mm *Excluding Column









Loci Collection

The flexible design of Loci has a distinctive lightness and transparency. With a clear linear profile based around square forms, the individual elements work well in groups due to their lightness of presence. Loci responds to the architecture of its time and its uniquely asymmetric design resonates through the full suite of products. The eye-catching 'ribbon' element offers enormous potential for creativity and flexibility.





















elements there to "control" them.











GEO Collection



2. BENCH

L - 1800 mm, H - 440 mm, W - 675 mm



GEO Collection

GEO seating reflects the best of modern urban design: simple, sustainable and robust materials in a low profile form. The GEO seating range is contemporary, yet its simple discreet unobtrusive lines make it equally suited to both historical and modern settings.

Seating elements are manufactured from a combination of high quality Stainless Steel, Steel and Iroko Timber.







L - 600 mm, H - 1800 mm - 3000 mm



3. POST & RAIL

L - 1000, 1500 or 2000 mm, H - 1106mm, DØ - 76 mm

4. HOOP CYCLE STAND

L - 600 mm, H - 850, DØ - 50 mm

L - 900 mm, H - 850, DØ - 50 mm

GEO Collection

L - 1200 mm, H - 850, DØ - 50 mm

L - 1500 mm, H - 850, DØ - 50 mm

5. LITTER BIN

H - 1150 mm, DØ - 500 mm



H - 1100 mm, DØ - 102 mm, 140 mm, 204 mm

7. MARKER BOLLARD

H - 1100 mm, DØ - 140 mm

8. ILLUMINATED BOLLARD

H - 1100 mm, DØ - 140 mm, 204 mm

9. MONOLITH









GEO Collection

GEO features coordinated and cohesive Landscape Furniture designed to complement, rather than collide with, contemporary architectural styles.

The highest quality materials are used in GEO construction and are chosen with the knowledge that installation is disproportionately costly in relation to the furniture. This material choice decreases routine maintenance and replacement and therefore minimises the total lifetime cost.

The Litter Bin and Bollards are also available with integrated RhinoGuard® PAS 68 crash tested technology.















RAL 7035



Tramet has a simple, neutral design which dilutes into natural settings as well as urban and shopping contexts. Its main features focus on three aspects; comfort and adaptability to permit unconventional uses, excellent quality and versatile design.

The neutral design of Tramet allows it to blend into natural spaces as well as urban and commercial areas.















Tramet









L - 2500 mm, H - 840 mm, W - 570 mm

2. BENCH

L - 2500 mm, H - 440 mm, W - 560 mm

3. TABLE

L - 2500 mm, H - 800 mm, W - 914 mm

TRAMET Collection

Tramet has a simple, neutral design which dilutes into natural settings as well as urban and shopping contexts. Its main features focus on three aspects; comfort and adaptability to permit unconventional uses, excellent quality and versatile design.

The Tramet collection has a real and apparent robustness and sturdy feel. Benches may be installed free standing or surface fixed.

FSC*-certified timber is responsibly sourced from well managed forests (FSC* C133609)

The range comprises of a bench, seat and table responding to the demand for complimentary elements.



























Rendezvous Collection











1. SEAT

L - 1800 mm, H - 420 mm, W - 645 mm

2. BENCH

L - 1800 mm, H - 420 mm, W - 440 mm

3. CURVED BENCH

L - 1385 mm, H - 445 mm, W - 584 mm

4. LITTER BIN

H - 820 mm, DØ - 490 mm

5. TABLE

L - 1775 mm, H - 718 mm, W - 928 mm

/ineu graff

Exclusively supplied by

Street Furniture

Rendezvous Collection

The Rendezvous collection is manufactured using cast iron and hardwood from sustainable sources, treated using a unique timber treatment process. The timber is treated with an impregnator which protects the timber from ingress of water, algae and rot.



The mark of responsible forestry












*The timber is treated with a solvent free wood stain
















Unlimited combinations with Metrolinia



A curved configuration can be created using corner units



Create a social seating hub with a combination of seats, benches and planters



L - 600 mm, H - 456 mm, W - 600 mm

3. SEAT

L - 1200 mm, H - 456 mm, W - 600 mm

4. BENCH

L - 1200 mm, H - 456 mm, W - 600 mm

STEP 2 - Select Intermediates

Intermediate modules bring your design to life with the combination of seating and planting.

System components: Create your seating solution using the components below



To be used in the middle of a configuration only Not to be used at an immediate right angle with another seat

5. PLANTER










STEP 3 - Select Transition Modules

Transition modules are used to give added flexibility to your configuration to overcome the challenges of different landscapes



1. RADIUS END BLOCK

STEP 1 - Select End Module

End blocks are used to start or finish a configuration and can

be specified with either a radius corner or a square end.

L - 600 mm, H - 456 mm, W - 600 mm L - 600 mm, H - 456 mm, W - 600 mm

6. RADIUS CORNER BLOCK

L - 1200 mm, H - 456 mm, W - 1200 mm

7. INTERMEDIATE BLOCK (600)

L - 600 mm, H - 456 mm, W - 600 mm

INTERMEDIATE BLOCK (1200)

L - 1200 mm, H - 456 mm, W - 600 mm

8. CORNER BLOCK

L - 600 mm, H - 456 mm, W - 600 mm

9. X BLOCK

L - 600 mm, H - 456 mm, W - 600 mm

10. T BLOCK

L - 600 mm, H - 456 mm, W - 600 mm

Metrolinia Collection

The Metrolinia Collection is manufactured in precast concrete, with the option of Iroko timber slats for the seat and bench modules. The system comprises of "building blocks" to enable unlimited configurations of seats, benches and planters. Transition modules such as corner blocks, intermediate blocks and radius blocks can be incorporated into the scheme to navigate corners and more intricate spaces.

Select from 3 concrete finishes to ensure cohesion and visual consistency to suit the surrounding landscape.

Modular seating systems such as Metrolinia support the desire to create sociable spaces, where people can feel safe. Frequently used, visible spaces with a choice of modular concrete seating systems can support this.







MATERIALS/COLOURS


City Charcoal Grey City Grey















BOXLAND

Boxland is a modular system for arranging multiple aggregations covering all the components of the Box collection, as well as different accessory seat systems. The combination of the Box benches in their five lengths, together with the Box Planter and the Nexus pentagonal articulation element, allows infinity of simple or complex compositions that fit into any urban setting.









1. BOX 50

Boxland

L - 500 mm, H - 450 mm, W - 500 mm

2. BOX 100

L - 1000 mm, H - 450 mm, W - 500 mm

3. BOX 150

L - 1500 mm, H - 450 mm, W - 500 mm

4. BOX 200 L - 2000 mm, H - 450 mm, W - 500 mm

5. BOX 200 (WITH SEAT INSERT)

L - 2000 mm, H - 450 mm, W - 500 mm

6. BOX 250

L - 2500 mm, H - 450 mm, W - 500 mm

7. BOX PLANTER L - 2000 mm, H - 450 mm, W - 500 mm

8. BOX NEXUS


L - 810 mm, H - 450 mm, W - 760 mm







MATERIALS/COLOURS







1. HOLLOW BENCH

L - 1200 mm, H - 440 mm, W - 600 mm

2. HOLLOW BLOK LH

L - 1000 mm, H - 440 mm, W - 600 mm

3. HOLLOW BLOK RH

L - 1500 mm, H - 440 mm, W - 600 mm

4. SQUARE BLOK

L - 2000 mm, H - 440 mm, W - 600 mm

5. TRANSITION BLOK

L - 1193 mm, H - 799 mm, W - 500 mm

6. CYCLE BLOK

L - 600 mm, H - 440 mm, W - 600 mm

7. PLANTER BLOK

L - 1200 mm, H - 440 mm, W - 600 mm

8. LITTER BIN

L - 500 mm, H - 805 mm, W - 500 mm


















Marshalls M3 Collection



1. SEAT

L - 1800 mm, H - 820 mm, W - 533 mm

2. CURVED SEAT

L - 2228 mm, H - 820 mm, W - 535 mm

3. BENCH

L - 1800 mm, H - 450 mm, W - 525 mm

4. CURVED BENCH

L - 2228 mm, H - 450 mm, W - 525 mm

5. BACK TO BACK

6. TABLE

L - 1800 mm, H - 750 mm, W - 700 mm

7. LITTER BIN

H - 650 mm, DØ - 435 mm

8. SERPENTINE BENCH

L - 3626 mm, H - 450 mm

L - 1800 mm, H - 820 mm, W - 1066 mm

The Festival Collection is also available as a powder coated, mild steel alternative to Marshalls M3.


FESTIVAL COLLECTION

Festival carries the same design language as Marshalls M3 but at a more cost effective price point.




Marshalls M3 Collection

Capacity 85 L or 110 L













FESTIVAL

The Marshalls Festival Collection is also available as a powder coated, mild steel alternative to . Marshalls M3.

Festival carries the same design language as Marshalls M3 but at a more cost effective price point.

The Festival seating range combines comfort and functionality, to deliver a high quality seating option for almost any type of scheme.










Festival Collection



1. SEAT

L - 1800 mm, H - 820 mm, W - 533 mm

2. CURVED SEAT

L - 2228 mm, H - 820 mm, W - 535 mm

3. BENCH

L - 1800 mm, H - 450 mm, W - 525 mm

4. CURVED BENCH

L - 2228 mm, H - 450 mm, W - 525 mm

5. BACK TO BACK

L - 1800 mm, H - 820 mm, W - 1066 mm

6. TABLE

L - 1800 mm, H - 750 mm, W - 700 mm

7. LITTER BIN

H - 650 mm, DØ - 435 mm


8. SERPENTINE BENCH

L - 3626 mm, H - 450 mm

Marshalls Festival Collection

The Festival range is a versatile modular system that meets the demands of modern environments and enhances public spaces. Straight and curved seats and benches can be designed to any length, any internal radius above 600mm and in any combination. The Festival range is popular in education and healthcare establishments, and civic spaces.

MADE IN BRITAIN







MATERIALS/COLOURS

 $\sqrt{}$ FSC www.fsc.org F8C* C122084

The mark of responsible forestry















/ineu

4. WIDE BENCH

L - 1780 mm, H - 450 mm, W - 690 mm

5. SLIM BENCH

L - 1780 mm, H - 450 mm, W - 365 mm

6. CURVED BENCH

L - 1786 mm, H - 448 mm, W - 553 mm

Idylle Collection

The cast iron leg design gives the illusion of a tree trunk rising out of the ground. The unstained hardwood gives a natural aesthetic that will gradually blend into the environment.

Available in FSC®-certified timber or non FSC®-certified timber.

L - 1780 mm, H - 825 mm, W - 710 mm

2. CURVED BENCH WITH BACKREST

L - 1786 mm, H - 688 mm, W - 553 mm

3. CHAIR

IDYLLE

nature and natural forms.


Idylle is a biophilic inspired seating solution designed by French designer Arturo Erbsman, whose designs reflects

L - 715 mm, H - 810 mm, W - 635 mm

Street Furniture













Waterside Collection

2. LITTER BIN

1.SEAT

H - 1000 mm, W - 175 mm

L - 2110 mm, H - 871 mm, W - 893 mm

L - 850 mm, H - 1015 mm, W - 450 mm

4. CYCLE STAND H - 850 mm, W - 460 mm



5. POST AND RAIL

L - 2000 mm, H - 1200 mm









5 Rail 6 Rail

The Waterside Post and Rail system is available as a 3, 4, 5 or 6 rail unit to suit the aesthetic requirements of a project.

Waterside Collection


The Waterside collection, manufactured from Ferrocast*, is defined by sleek elliptical forms that allow the range to sympathetically blend into the landscape.


The extremely durable Ferrocast® material enables the range to be perfectly suited for challenging environments such as seafronts. Due to the unique polyurethane chemical composition, the material will not rust or corrode.

A steel core gives the products internal strength for optimum durability.





















1. SEAT

L - 1920 mm, H - 880 mm, W - 496 mm

2. BENCH

L - 1920 mm, H - 470 mm, W - 496 mm

3. TABLE

L - 1920 mm, H - 700 mm, W - 596 mm



Coda Collection

The Coda collection, manufactured from wet cast concrete is available in two colour tones which coordinate with Marshalls Metrolinia and Conservation paving.

All metal items are finished with a highly durable polyester powder coat in RAL 9007.



MATERIALS/COLOURS


















Igneo Collection



1. SEAT*

L - 3176 mm, H - 878 mm, W - 1115 mm

2. CHAIR

L - 953 mm, H - 434mm, W - 561 mm

3. STOOL

L - 500 mm, H - 500 mm, W - 500 mm

4. LITTER BIN

L - 900 mm, H - 1170 mm

5. SEAT MODULES

LEFT HAND - L - 1037 mm, H - 878 mm, W - 1115 mm INTERMEDIATE - L - 1037 mm, H - 878 mm, W - 1115 mm RIGHT HAND - L - 1037 mm, H - 878 mm, W - 1115 mm ARM REST MODULE - L - 60 mm, H - 670 mm, W - 1115 mm





Customise the Igneo seat to fit your scheme





Step 3 Select number of intermediate modules

Step 4 Select number of arm rests

Igneo Collection

Igneo is a coordinated concrete modular system that offers contemporary styling, combined with functionality and maximum robustness. The collection consists of a seat, chair, stool and a litter BRITAIN bin. The seating can be specified to any length, based on the module sizes, dependent on the location and the number of seating places

Manufactured in Ferrocast®, the seating arm rests and litter bin doors will have a long life span and require virtually no maintenance. Ferrocast® parts can be ordered in any standard RAL colour.



of material

MATERIALS / COLOURS









Add extra modules to


extend the system













DEMETRA


Understanding outdoor spaces and bringing them to life, this stylish and durable range offers comfort and amenity to all users.

The Demetra modular system is a contemporary and flexible range which comprises of a bench with a choice of timber seating options, curved bench, planter and a combined seating/ planter unit.

Together these items can be mixed and matched to provide the perfect configuration for any project.











2. BENCH WITH SLATS

L - 1800 mm, H - 480 mm, W - 600 mm

Demetra Collection

3. BENCH

1. SEAT

L - 1800 mm, H - 480 mm, W - 600 mm

L - 1800 mm, H - 812 mm, W - 600 mm

Small: L - 1705 mm, H - 480 mm, W - 775 mm Large: L - 1907 mm, H - 480 mm, W - 742 mm

L - 1764 mm, H - 480 mm, W - 1705 mm

Also available with one single timber seat insert

7. CURVED PLANTER

L - 1907 mm, H - 480 mm, W - 742 mm

8. COMBINED SEAT & PLANTER

L - 2249 mm, H - 1664 mm, W - 400 mm

Exclusively supplied by













4. DEMETRA CURVED

Create a social space with modules from the Demetra range

6. PLANTER

L - 1800 mm, H - 470 mm, W - 600 mm

Demetra Collection

The Demetra modular system is a contemporary and flexible range that comprises of a bench with a choice of timber seating options, curved bench, planter and a combined seating/planter unit.

All units have been designed to be connected together without the need for fixings giving greater design freedom and ease of installation.

MATERIALS/COLOURS*













Stone and Concrete colours are available in a choice of finishes, including Sandblasted, Polished, Bush




Urbain® is a modular seating system designed to fit perfectly into a number of urban settings. The collection comprises of an interchangeable bench, seat and table allowing for greater modification. The customisable seating arrangement includes a breadth of options ranging from armrests, single, double and triple backrest variations and table attachments. The multiple leg options enable double benches as well as angled corner pieces to create dynamic runs. Urbain® is created using FSC®-certified softwood and the mild steel can be customised with a range of RAL or fossil effect powder





Urbain® Collection



1. SEAT

L - 2400 mm, H - 845 mm, W - 500 mm

2. SEAT WITH ARMS

L - 2400 mm, H - 845 mm, W - 500 mm

3. BENCH

L - 2400 mm, H - 450 mm, W - 500 mm

4. BENCH WITH ARMS

L - 2400 mm, H - 640 mm, W - 500 mm

5. SEAT WITH DOUBLE BACKREST

L - 2400 mm, H - 845 mm, W - 500 mm

6. SEAT WITH DOUBLE BACKREST AND ARMS

L - 2400 mm, H - 845 mm, W - 500 mm

7. SEAT WITH TWO SINGLE BACKRESTS

L - 2400 mm, H - 845 mm, W - 500 mm

8. SEAT WITH TWO SINGLE BACKRESTS & TABLE

L - 2400 mm, H - 845 mm, W - 500 mm

9. TABLE

L - 2400 mm, H - 750 mm, W - 500 mm



The design possibilities are endless with the Urbain® seating system.

Available in a range of standard configurations, Urbain* is also completely modular, offering unlimited flexibility.

Select from a choice of bench or seat legs and a range of backrests and customisable extras. Create shapes with 45°, 90° or end to end mild steel connectors, available in a selection of 7 colour variations to complement your scheme.









MATERIALS/COLOURS*



















Mobile Gardens



Dimensions (mm)	1500 x 1500
Capacity (L)	407
Materials	Timber and powder coated steel
Finish options	Wood finish options
Extra features	With or without back rest

Different seating layouts available



MOBILE GARDEN SEATING

	4080 x 4080	mensions (mm)
	1020	pacity (L)
Unstained Ha	Timber and powder coated steel	aterials
	Wood finish options	nish options
	With or without backrest	tra features
Walnu		





Planters







CLASSICA

Height (mm)	470
Width x Length (mm)	600 x 1800
Capacity (L)	330
Materials	Precious stone or concrete
Options	Available as part of a range with complimentary products

leight (mm)	600	Height (mm)	650
Width x Length (mm)	700 x 1980	Width x Length/ø (mm)	1220/1620
Capacity (L)	483	Capacity (L)	300/600
Materials	Precious stone	Materials	Precious stone Concrete
Options	Eight colour options	Options	Two size options Eight colour options

BOULEVARD



STRADA



NET

Height (mm)	730
Width x Length/ø (mm)	1200
Materials	Concrete
Options	Height can be increased by adding extra rings A variety of shapes available

Height (mm)	500
Width x Length/ø (mm)	710
Materials	Concrete
Options	Available as square or circular planters

Height (mm)	820
Width x Length/ø (mm)	710
Capacity (L)	120
Materials	Precious stone

Planters



Height (mm)	400
Width x Length/ø (mm)	2370
Capacity (L)	315
Materials	Acid etched concrete


Height (mm)	380
Width x Length/ø (mm)	4260 x 2350
Capacity (L)	1214
Materials	Acid etched concrete

Height (mm)	500
Width x Length (mm)	450 x 2000
Capacity (L)	220
Materials	Concrete

OPTIMA



ROOTS



RENDEZVOUS



Height (mm)	620 / 620 / 920 / 960 / 1300
Width x Length (mm)	640 x 640 / 640 x1280 / 920 x 920 / 1100 x 1100 / 1400 x 1400
Capacity (L)	80 / 200 / 350 / 490 / 1080
Materials	Steel and FSC®-certified hardwood
Options	Steel - standard RAL, FSC®-certified hardwood - natural

640 / 640 / 900 / 950 / 1200
640 x 640 / 640 x 1280 / 920 x 920 / 1100 x 1100 / 1400 x 1400
80 / 200 / 350 / 490 / 1080
Steel
Laser cut

ight (mm)	930 / 1030	
dth x Length (mm)	860 x 860 / 1080 x 1080	ı
oacity (L)	190 / 480	
terials	Steel and FSC®-certified hardwood with shade protection	ı
tions	Two size options	ı

DETER

Seating







SIT SEAT

leight (mm)	900	Height (mm)	580	Height (mm)	770
Vidth x Length (mm)	2000 x 4000	Width x Length (mm)	1400 x 3250	Width x Length (mm)	390 x 2200
Naterials	Concrete	Materials	Concrete	Materials	Concrete
Brand	Escofet	Brand	Escofet	Brand	Escofet







Height (mm)	450
Width x Length (mm)	650 x 2000
Materials	Slim concrete
Brand	Bellitalia

leight (mm)	450	Height (mm)
Vidth x Length (mm)	769 x 1940	Width x Leng
Materials	Slim concrete	Materials
Brand	Bellitalia	Brand



				_		
Height (mm)	738	Height (mm)	450		Height (mm)	450
Width x Length (mm)	634 x 3756	Width x Length (mm)	634 x 2114		Width x Length (mm)	540 x 1990
Materials	Slim concrete	Materials	Precious stone and timber		Materials	Slim concrete
Brand	Bellitalia	Brand	Bellitalia		Brand	Bellitalia




Height (mm)	847	Height (mm)	450	Height (mm)	400
Width x Length (mm)	450 x 449	Width x Length (mm)	450 x 449	Width x Length (mm)	1456 x 2550
Materials	Slim concrete	Materials	Slim concrete	Materials	Precious stone
Brand	Bellitalia	Brand	Bellitalia	Brand	Bellitalia
















U-SHAPE BENCH
BENCH

Height (mm)	450
Width x Length (mm)	1150 x 1890
Materials	Concrete
Brand	Escofet

Height (mm)	450
Width x Length (mm)	600 x 2200
Materials	Slim concrete and timber
Brand	Escofet

leight (mm)	450
vidth x Length (mm)	1000 x 4000
laterials	Concrete and timber
rand	Escofet

Height (mm)	890
Width x Length (mm)	1000 x 4000
Materials	Concrete and timber
Brand	Escofet

Height (mm)	880	Height (mm)	480
Width x Length (mm)	420 x 2980	Width x Length (mm)	600 x 2000
Materials	Concrete and timber	Materials	Concrete an
Brand	Escofet	Brand	Escofet

Concrete

Marshalls

MADE IN BRITAIN

Height (mm)

Materials

Brand

Width x Length (mm)


1059 x 1059

Concrete

Marshalls



-	_	_
	Height (mm)	500
	Width x Length (mm)	500 x 500
	Materials	Concrete
	Brand	Marshalls



450

600 x 2200 / 860 x 2960

2 sizes available

Escofet

Height (mm)

Materials

Options

Brand

Width x Length (mm)



BARANA



BS.1

Height (mm)	500	Height (mm)	420
Width x Length (mm)	800 x 2000	Width x Length (mm)	500 x 1750
Materials	Concrete	Materials	Concrete
Brand	Escofet	Brand	Escofet

Height (mm)	420
Width x Length (mm)	500 x 1750
Materials	Concrete
Brand	Escofet

Height (mm)

Materials

Brand

Width x Length (mm)

CANET BENCH LABYRINTH BENCH LABYRINTH CUBE Height (mm) Height (mm) Height (mm) 860 x 2960 Width x Length (mm) 450 x 1500 Width x Length (mm) 450 x 450 Width x Length (mm) Materials Materials Precious stone Materials Concrete Precious stone Brand Brand Brand Escofet Bellitalia Bellitalia



Height (mm)	450	Height (mm)	450	Height (mm)	500
Width x Length (mm)	1500 x 1500	Width x Length (mm)	1500 x 1500	Width x Length (mm)	500 x 2000
Materials	Precious stone	Materials	Precious stone	Materials	Natural stone
Brand	Bellitalia	Brand	Bellitalia	Brand	Marshalls

STONELEMENTS BENCH

STONELEMENTS CURVED BENCH

STONELEMENTS SEAT



CODA



CODA BENCH



Height (mm)	450
Width x Length (mm)	600 x 2000
Materials	Natural stone
Brand	Marshalls

Height (mm)	450	Height (mm)
Width x Length (mm)	770 x 2242	Width x Leng
Materials	Natural stone	Materials
Brand	Marshalls	Brand

Height (mm)	700
Width x Length (mm)	600 x 2000
Materials	Natural stone
Brand	Marshalls

Height (mm)	880
Width x Length (mm)	496 x 1920
Materials	Concrete and timber
Options	Armrest is available
Brand	Marshalls

Height (mm)	690	
Width x Length (mm)	496 x 1920	
Materials	Concrete and timber	
Options	Armrest is available	
Brand	Marshalls	















ERACLEA WITH FULL TIMBER





VENEZIA BENCH

Height (mm)	450
Width x Length (mm)	610 x 2200
Materials	Precious stone
Brand	Bellitalia

Height (mm)	450	Height (mm)	784
Width x Length (mm)	610 x 2200	Width x Length (mm)	610 x 2200
Materials	Precious stone and timber	Materials	Precious stone and timber
Brand	Bellitalia	Brand	Bellitalia

Height (mm)	784
Width x Length (mm)	610 x 2200
Materials	Precious stone and timber
Brand	Bellitalia

Height (mm)	450	Height (mm)	450
Width x Length (mm)	610 x 2200	Width x Length (mm)	450 x 1900
Materials	Precious stone and porcelain	Materials	Precious stone
Brand	Bellitalia	Brand	Bellitalia








600 x 1800

Bellitalia

DEMETRABENCH WITH SLATS

Height (mm)	480		Height (mm)	480		Height (mm)
Width x Length (mm)	600 x 1800		Width x Length (mm)	600 x 1800		Width x Length (mm
Materials	Precious stone		Materials	Precious stone and timber		Materials
Brand	Bellitalia		Brand	Bellitalia		Brand
\ 	Width x Length (mm) Materials	Width x Length (mm) 600 x 1800 Materials Precious stone	Width x Length (mm) 600 x 1800 Materials Precious stone	Width x Length (mm) 600 x 1800 Width x Length (mm) Materials Precious stone Materials	Width x Length (mm) 600 x 1800 Width x Length (mm) 600 x 1800 Materials Precious stone Materials Precious stone and timber	Width x Length (mm) 600 x 1800 Waterials Precious stone Materials Precious stone and timber



















DEMETRAY BENCH



DEMETRACOMBINED SEAT AND PLANTER



Height (mm)	480
Width x Length (mm)	775 x 1705
Materials	Precious stone
Brand	Bellitalia


leight (mm)	480	Height (mm)	400
Vidth x Length (mm)	1705 x 1764	Width x Length (mm)	1664 x 2249
Materials	Precious stone	Materials	Precious stone and timber
Brand	Bellitalia	Brand	Bellitalia

METROLINIA SEAT



METROLINIA BENCH

METROLINIA INTERMEDIATE BLOCK (600)



Height (mm)	811
Width x Length (mm)	600 x 1200
Materials	Concrete and timber
Brand	Marshalls

Height (mm)	450
Width x Length (mm)	600 x 1200
Materials	Concrete and timber
Brand	Marshalls

Height (mm)	456	
Width x Length (mm)	600 x 600	
Materials	Concrete	
Brand	Marshalls	







Height (mm)	456
Width x Length (mm)	600 x 1200
Materials	Concrete
Brand	Marshalls

Height (mm)	456	Height (mm)	460
Width x Length (mm)	1200 x 1200	Width x Length (mm)	380 x 1600
Materials	Concrete	Materials	Steel and timber
Brand	Marshalls	Brand	Marshalls



MADE IN BRITAIN







Height (mm)	800
Width x Length (mm)	455 x 1600
Materials	Steel and timber
Brand	Marshalls

Height (mm)	800
Width x Length (mm)	455 x 600
Materials	Steel and timber
Brand	Marshalls

Height (mm)	590
Width x Length (mm)	380 x 600
Materials	Steel and timber
Brand	Marshalls

DETER

Seating







Height (mm)	800	Height (mm)	800	Height (mm)	812
Width x Length (mm)	550 x 725	Width x Length (mm)	550 x 1925	Width x Length (mm)	571 x 1812 / 571 x 19
				Materials	Steel & FSC®-certified
Materials	Steel and timber	Materials	Steel and timber	Options	2 place / 3 place seat
Brand	Escofet	Brand	Escofet	Brand	Sineu Graff







Height (mm)	450
Width x Length (mm)	328 x 1812
Materials	Steel & FSC®-certified timber
Brand	Sineu Graff


Height (mm)	812
Width x Length (mm)	513 x 562
Materials	Steel & FSC®-certified timber
Brand	Sineu Graff

Height (mm)	871
Width x Length (mm)	888 x 2110
Materials	Ferrocast® and timber
Options	Armrest is available
Brand	Marshalls













TWIST
3 PLACE SEAT



TWIST 2 PLACE SEAT

Height (mm)	456
Width x Length (mm)	518 x 1323
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff

Height (mm)	803
Width x Length (mm)	541 x 1752
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff

Height (mm)	803
Width x Length (mm)	541 x 1202
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff





TWIST BENCH AND CHAIR



840

Escofet

Steel and FSC®-certified timber

ength (mm) 570 x 2500

TRAMET SEAT

Height (mm)	803
Width x Length (mm)	541 x 652
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff

Height (mm)	803	Height (mr
Width x Length (mm)	541 x 1200	Width x Le
Materials	Cast iron & FSC®-certified timber	Materials
Brand	Sineu Graff	Brand

TRAMET BENCH





MADE IN BRITAIN

PARKWAY BENCH

Height (mm)	440
Width x Length (mm)	560 x 2500
Materials	Steel and FSC®-certified timber
Brand	Escofet

Height (mm)	972
Width x Length (mm)	635 x 1800
Materials	Ferrocast® and timber
Options	Arm rest is available
Brand	Marshalls

Height (mm)	482
Width x Length (mm)	537 x 1800
Materials	Ferrocast® and timber
Options	Arm rest is available
Brand	Marshalls







LINK 2 PLACE SEAT

Height (mm)	430
Width x Length (mm)	420 x 1000
Materials	FSC®-certified timber and steel
Brand	Sineu Graff

Height (mm)	430	
Width x Length (mm)	420 x 1500	
Materials	FSC®-certified timber and steel	
Brand	Sineu Graff	

Height (mm)	430
Width x Length (mm)	490 x 1000
Materials	FSC®-certified timber and steel
Brand	Sineu Graff







LINKPERCH SEAT



LINK STOOL


	0
Width x Length (mm) 490	0 x 1500
Materials FS0	C°-certified timber and steel
Brand Sin	neu Graff

Height (mm)	880
Width x Length (mm)	420 x 468
Materials	FSC®-certified timber and steel
Brand	Sineu Graff

Height	(mm)	430
Width x	Length (mm)	420 x 435
Materia	ls	FSC®-certified timber and steel
Brand		Sineu Graff

DETER

Seating







RENDEZVOUS SEAT

Height (mm)	960
Width x Length (mm)	710 x 1820
Materials	FSC®-certified timber and steel
Brand	Sineu Graff


Height (mm)	375	Height (mm)	420
Width x Length (mm)	2015 x 3200	Width x Length (mm)	440 x 1800
Materials	FSC®-certified timber and steel	Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff	Brand	Sineu Graff







RENDEZVOUS
CURVED BENCH



FLOR BENCH

Height (mm)	420
Width x Length (mm)	440 x 1800
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff

Height (mm)	445
Width x Length (mm)	584 x 1385
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff

Height (mm)	420
Width x Length (mm)	2395 x 2662
Materials	Precious stone or white granite
Brand	Bellitalia







Height (mm)	430
Width x Length (mm)	2370 x 1930
Materials	Concrete
Brand	Escofet

Height (mm)	460	Height (mm)	840
Width x Length (mm)	2370 x 1930	Width x Length (mm)	605 x 1800
Materials	Plastic	Materials	Cast iron & timber
Brand	Escofet	Brand	Marshalls





GEO BENCH



Height (mm)	768
Width x Length (mm)	525 x 1800
Materials	Stainless steel & timber
Options	Arm rest is available
Brand	Marshalls

Height (mm)	440
Width x Length (mm)	675 x 1800
Materials	Stainless steel & timber
Options	Arm rest is available
Brand	Marshalls

Height (mm)	878
Width x Length (mm)	650 x 1528
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff







Height (mm)	878
Width x Length (mm)	852 x 1940
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff

Height (mm)	405	Height (mm)
Width x Length (mm)	390 x 1940 / 630 x 1940	Width x Lend
Materials	Cast iron & FSC®-certified timber	
Options	Slim / wide benches available	Materials
Brand	Sineu Graff	Brand

Height (mm)	878
Width x Length (mm)	1704 x 1940
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff







Height (mm)	820
Width x Length (mm)	533 x 1800
Materials	Stainless steel
Brand	Marshalls

Height (mm)	825
Width x Length (mm)	519 x 2021
Materials	Stainless steel
Brand	Marshalls

Height (mm)	820
Width x Length (mm)	1066 x 1800
Materials	Stainless steel
Brand	Marshalls







Height (mm)	450
Width x Length (mm)	525 x 1800
Materials	Stainless steel
Brand	Marshalls

Height (mm)	450	
		V
Width x Length (mm)	525 x 1800	v
		\ \
Materials	Stainless steel	
		C
Brand	Marshalls	Е
Bruna	Marshans	L L

Height (mm)	820
Width x Length (mm)	533 x 1800
Materials	Steel
Options	Available in standard RAL colours
Brand	Marshalls







FESTIVAL BENCH

Height (mm)	820
Width x Length (mm)	535 x 2970
Materials	Steel
Options	Available in standard RAL colours
Brand	Marshalls

Height (mm)	820
Width x Length (mm)	1066 x 1800
Materials	Steel
Options	Available in standard RAL colours
Brand	Marshalls

Height (mm)	450
Width x Length (mm)	525 x 1800
Materials	Steel
Options	Available in standard RAL colours
Brand	Marshalls





URBAN CITY PERCH SEAT



URBAN CITY 3 PLACE BENCH



URBAN CITY 2 PLACE BENCH



URBAN CITY SINGLE SEAT



PRAT STOOL

Height (mm)	450
Width x Length (mm)	525 x 2037
Materials	Steel
Options	Available in standard RAL colours
Brand	Marshalls

Height (mm)	905	Height (mm)
Width x Length (mm)	290 x 1000	Width x Leng
Materials	Steel or stainless steel	Materials
Brand	Sineu Graff	Brand

Height (mm)	765
Width x Length (mm)	570 x 1700
Materials	Steel or stainless steel
Brand	Sineu Graff

Height (mm)	765
Width x Length (mm)	570 x 1100
Materials	Steel or stainless steel
Brand	Sineu Graff

Height (mm)	765
Width x Length (mm)	570 x 500
Materials	Steel or stainless steel
Brand	Sineu Graff

Height (mm)	450
Width x Length (mm)	450 x 450
Materials	Concrete
Options	Table available
Brand	Escofet








Height (mm)	580	
Width x Length (mm)	1017 x 2013	
Materials	Concrete	
Brand	Bellitalia	

Height (mm)	830	Height (mm)	765
Width x Length (mm)	845 x 828	Width x Length (mm)	570 x 1820
Materials	Concrete	Materials	Concrete
Brand	Bellitalia	Brand	Bellitalia







QUADRO

765
570 x 1100
Concrete
Bellitalia

Height (mm)	700	Height (mm)
Width x Length (mm)	550 x 550	Width x Leng
Materials	Concrete	Materials
Brand	Escofet	Brand

Height (mm)	450
Width x Length (mm)	500 x 500
Materials	Precious stone
Brand	Bellitalia





MADE IN BRITAIN





Height (mm)	500
Width x Length (mm)	468 x 570
Materials	Steel & FSC®-certified timber
Options	Illuminated end panel available
Brand	Marshalls

Height (mm)	899
Width x Length (mm)	500 x 1790
Materials	Steel & FSC®-certified timber
Options	Illuminated end panel available
Brand	Marshalls

Height (mm)	899
Width x Length (mm)	500 x 1640
Materials	Steel & FSC®-certified timber
Brand	Marshalls





NATURAL ELEMENTS
CONVEX BENCH MODULE

NATURAL ELEMENTS 45° RADIUS CORNER



Height (mm)	450 - 500
Width x Length (mm)	500 x 1640
Materials	Steel & FSC®-certified timber
Options	Illuminated end panel available
Brand	Marshalls

Height (mm)	500 - 550
Width x Length (mm)	500 x 1640
Materials	Steel & FSC®-certified timber
Brand	Marshalls

Height (mm)	500
Width x Length (mm)	500 x 881
Materials	Steel & FSC®-certified timber
Brand	Marshalls







Height (mm)	810	Height (mm)	810	Height (mm)	767
Vidth x Length (mm)	610 x 1220 / 610 x 1770	Width x Length (mm)	610 x 670	Width x Length (mm)	450 x 2012
Materials	Cast iron & FSC®-certified timber	-			
Options	2 place / 3 place seat available	Materials	Cast iron & FSC®-certified timber	Materials	Cast aluminium & timber
Brand	Sineu Graff	Brand	Sineu Graff	Brand	Marshalls







Height (mm)	637
Width x Length (mm)	450 x 2012
Materials	Cast aluminium & timber
Brand	Marshalls

Height (mm)	825
Width x Length (mm)	710 x 1780
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff

Height (mm)	810
Width x Length (mm)	635 x 715
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff







IDYLLE CURVED BENCH

Height (mm)	450	Height (mm)	450		Height (mm)	448
Width x Length (mm)	690 x 1780	Width x Length (mm)	365 x 1780		Width x Length (mm)	552 x 1768
Materials	Cast iron & FSC®-certified timber	Materials	Cast iron & FSC®-certified timber		Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff	Brand	Sineu Graff		Brand	Sineu Graff







Height (mm)	688
Width x Length (mm)	553 x 1768
Materials	Cast iron & FSC®-certified timber
Brand	Sineu Graff

Height (mm)	845	He
Width x Length (mm)	500 x 2400	Wi
Materials	Mild steel & FSC®-certified softwood	Ma
Brand	Marshalls	Bra

Height (mm)	845
Width x Length (mm)	500 x 2400
Materials	Mild steel & FSC®-certified softwood
Brand	Marshalls







Height (mm)	450	Height (mm)	640	Height (mm)	845
Width x Length (mm)	500 x 2400	Width x Length (mm)	500 x 2400	Width x Length (mm)	500 x 2400
Materials	Mild steel & FSC®-certified softwood	Materials	Mild steel & FSC®-certified softwood	Materials	Mild steel & FSC®-certified softwood
Brand	Marshalls	Brand	Marshalls	Brand	Marshalls







Height (mm)	845
Width x Length (mm)	500 x 2400
Materials	Mild steel & FSC®-certified softwood
Brand	Marshalls

Height (mm)	845
Width x Length (mm)	500 x 2400
Materials	Mild steel & FSC®-certified softwood
Brand	Marshalls

Height (mm)	845	
Width x Length (mm)	500 x 2400	
Materials	Mild steel & FSC®-certified softwood	
Brand	Marshalls	















Height (mm)	796
Width x Length (mm)	570 x 1800
Materials	Mild steel & FSC®-certified timber
Brand	Sineu Graff

Height (mm)	796
Width x Length (mm)	570 x 1200
Materials	Mild steel & FSC®-certified timber
Brand	Sineu Graff

Height (mm)	744
Width x Length (mm)	625 x 1942
Materials	Mild steel & FSC®-certified timber
Brand	Sineu Graff







Height (mm)	738	Height (mm)	450	Н	leight (mm)	450
Width x Length (mm)	615 x 1961	Width x Length (mm)	462 x 466	W	Vidth x Length (mm)	518 x 1569
Materials	Cast iron & FSC®-certified timber	Materials	FSC®-certified hardwood & steel	M	Materials	FSC®-certified hardwood & steel
Brand	Sineu Graff	Brand	Sineu Graff	В	Brand	Sineu Graff






Height (mm)	766
Width x Length (mm)	564 x 1569
Materials	FSC®-certified hardwood & steel
Brand	Sineu Graff

Height (mm)	766	Heig
Width x Length (mm)	564 x 1569	Widt
Materials	FSC®-certified hardwood & steel	Mate
Brand	Sineu Graff	Bran

Height (mm)	450
Width x Length (mm)	674 x 1800
Materials	FSC®-certified hardwood & steel
Brand	Sineu Graff

Sineu Graff

Seating



Sineu Graff

Brand

Escofet


Brand




Height (mm)	822	Height (mm)	710	Height (mm)	845
Width x Length (mm)	788 x 1500	Width x Length (mm)	845 x 1030	Width x Length (mm)	500 x 2400
Materials	Zinc plated steel & UHPC concrete	Materials	Concrete	Materials	Concrete
Brand	Escofet	Brand	Escofet	Brand	Escofet

Brand





BOX 200 BENCH



BOX NEXUS



Height (mm)	450
Width x Length (mm)	500 x 500 / 1000 / 1500 / 2000 / 2500
Materials	Concrete
Brand	Escofet

Height (mm)	450	Heio
Width x Length (mm)	760 x 810	Wid
Materials	Concrete and larch/HPL	Mat
Brand	Escofet	Brar

leight (mm)	450
Vidth x Length (mm)	760 x 810
Materials	Concrete
Brand	Escofet



Tables







Height (mm)	760	Height (mm)	750	Height (mm)	750
Width x Length (mm)	745 x 1600	Width x Length (mm)	700 x 1800	Width x Length (mm)	700 x 1800
Materials	Ferrocast® and Timber	Materials	Stainless steel	Materials	Mild steel
Brand	Marshalls	Brand	Marshalls	Brand	Marshalls





LINK LOW



LINK PERCH SEAT AND HIGH TABLE

Height (mm)	735
Width x Length (mm)	855 x 2000
Materials	FSC®-certified timber & steel
Brand	Sineu Graff

Height (mm)	370
Width x Length (mm)	850 x 850
Materials	FSC®-certified timber & steel
Brand	Sineu Graff

Height (mm)	1100
Width x Length (mm)	435 x 435
Perch seat dimensions	H 880, W 420 x L 268
Materials	FSC®-certified timber & steel
Brand	Sineu Graff



RENDEZVOUS



SPRING



Height (mm) Materials FSC®-certified timber Sineu Graff Brand


Height (mm)	718
Width x Length (mm)	928 x 1775
Materials	FSC®-certified timber & cast iron
Brand	Sineu Graff

Height (mm)	750
Width x Length (mm)	900 x 2250
Materials	Ultratense Concrete®
Brand	Bellitalia

TRAMET



PRIMA MARINA



TWIST



Height (mm)	800
Width x Length (mm)	914 x 2500
Materials	Timber & steel
Brand	Escofet

Height (mm)	750
Width x Length (mm)	900 x 2200
Materials	Slimline™ Concrete & timber
Brand	Escofet

Height (mm)	456
Width x Length (mm)	477 x 652
Materials	FSC®-certified timber & cast iron
Brand	Sineu Graff

Tables

TWIST CURVED TABLE







CODA

Height (mm)	456
Width x Length (mm)	517 x 857
Materials	FSC®-certified timber & cast iron
Brand	Sineu Graff

timber

OPTIMA



Height (mm)	700
Width x Length (mm)	832 x 1816
Materials	Steel & FSC®-certified timber
Brand	Sineu Graff

FRUITS



Height (mm)	700
Diameter (mm)	800
Materials	FSC®-certified timber & cast iron
Brand	Sineu Graff



Litter Bins









Dimensions (mm)	780(h) x 400 (ø) 50		Dimensions (mm)	1228(h) >
Capacity (L)			Capacity (L)	130
Materials	RAL coated mild		Materials	Steel
	steel or Stainless Steel		Finish options	Jet Black
				Bespoke
Extra features Root fix or surface mount			Extra features	Ashtray, colours a

Dimensions (mm)	1228(h) x 566 (ø)
Capacity (L)	130
Materials	Steel
Finish options	Jet Black RAL 9005
Extra features	Bespoke branding, Ashtray, other RAL colours available as extra

Dimensions (mm)	1010(h) x 550 / 780 (l)
Capacity (L)	90 / 160
Materials	Stainless Steel
Extra features	Single or double bins available

Dimensions (mm)	1010(h) x 555(l)
Capacity (L)	120
Materials	Steel
Finish options	Jet Black RAL 9005

ALBION SQUARE

BOULEVARD



Dimensions (mm)

Capacity (L)

Finish options

Extra features

Materials

1000(h) x 500(ø)

Choice of colours

Concrete

and finishes

Lid available



Dimensions (mm)

Capacity (L)

Finish options

Extra features

Materials

810(h) or 912(h) x 420(ø)

Steel & Hardwood

Powder coated steel options

Two sizes available

48 or 58

CLASSIC ROUND

•	

CLASSIC SQUARE

CONSORT PLASTIC

Dimensions (mm)	630(h) x 360 x 3 710(h) x 392 x 3
Capacity (L)	42 or 59
Materials	Steel & Hardwo
Finish options	Powder coated options
Extra features	Two sizes availa

Dimensions (mm)	810(h) x 500(ø)
Capacity (L)	100
Materials	Medium Density Polyethylene
Finish options	Any standard colour
Extra features	Stubber plate or Plastic Liner

CONTEMPORARY

TOP APERTURE (Empty via front)



CONTEMPORARY

FRONT APERTURE (Empty via top)



CONTEMPORARY

TOP APERTURE (Empty via top)



CONTEMPORARY



nsions (mm) | 780(h) x 360(d) x 500(w)

finish options

liner holder

Steel or stainless steel

A range of colour and

Standard: Stainless steel

liner. Extra: ashtray & bin

Dimensions (mm) | 880(h) x 420(ø) Capacity (L) Materials Steel or stainless steel A range of colour and Finish options finish options Stainless steel liner as Extra features

Dimensions (mm)	730(h) x 500(ø)	
Capacity (L)	40	
Materials	Steel or stainless steel	
Finish options	A range of colour and finish options	
Extra features	Stainless steel liner and ashtray as standard	

Dimensions (mm)	780(h) x 500(ø)	Dir	mei
Capacity (L)	70	Ca	pac
Materials	Steel or stainless steel	Ma	ater
Finish options	A range of colour and finish options	Fin	nish
Extra features	Standard: Stainless steel liner. Extra: ashtray & bin liner holder	Ext	tra

SEMI CIRCULAR



Dimensions (mr
Capacity (L)
Materials
Finish options
Extra features

CONTEMPORARY

SLOPING LID

minimin

1010(h) x 450(ø)

Steel or stainless steel

A range of colour and

Buffered lid closure

Closing is automatic

finish options

Dimensions (mm) 770(h) x 420(ø) Capacity (L) Steel & Stainless Steel Diamond point Finish options embossed sheet metal Extra features 8 options available

DIAMOND POINT

Dimensions (mm) 843 (h) x 357(d) x 471(w) Capacity (L) Body, lid, stripe: Zinc and powder coated steel Cigarette snuffer: Stainless steel Materials

EASY

WALL MOUNTED, FRONT COLLECTION

EASY IJUMBO COMPATIBLE



Dimensions (mm)	475(ø) x 840 (h)
Capacity (L)	110
Materials	Body, lid, stripe: Zinc and powder coated steel Cigarette snuffer:





Dimensions (mm) 828(h) x 495(d) 470(w)

Body, lid, stripe: Zinc and powde coated steel Cigarette snuffe Stainless steel

Capacity (L)







) x	Dimensions (mm)	845(h) x 475(d) x 810(w)	Dimensions (mm)	651(h), 577(ø) / 859(h), 630(ø)		Dimensions (mm)	1087(h) x 500
	Capacity (L)	2 x 110	Capacity (L)	90 / 110		Capacity (L)	70
e:	Body, lid, stripe:	Materials	Steel	Materials			
der	er Zinc and powder coated steel Cigarette snuffer:	Finish options	Powder coated steel options		Materials	Stainless stee	
fer:				steel options			
	Stainless steel	Extra features	4 options available		Finish options	Bead blast	

HERITAGE CAST IRON





HERITAGE ROUND



HERITAGE SQUARE



LAUREL & HARDY

Dimensions (mm)	950(h) x 415(ø)
Capacity (L)	85
Materials	Cast iron
Finish options	Jet black RAL 9005 coated
Extra features	Lid & Contrast colour lettering

Dimensions (mm)	1071(h) x 570(ø)
Capacity (L)	100
Materials	Medium Density Polyethylene (MDPE)
Finish options	A range of colour options
Extra features	Gold bands as standard, Stubber plate and plastic liner available as extra

Dimensions (mm)	1220(h) x 615(d) x 615(w)
Capacity (L)	100
Materials	MDPE
Finish options	A range of colour options
Extra features	Gold bands and ballast cartridge as standard, stubber plate and plastic liner available as extra

Dimensions (mm)	960(h) x 480(ø)
Capacity (L)	70
Materials	Cast stone
Finish options	Available in two finishes
Extra features	Litter bin and ashtray

LOCI



М3

MONARCH



Dimensions (mm)	860(h) x 450(d) x 450(w)
Capacity (L)	80
Materials	Galvanised steel & Ash timber
Extra features	Co-ordinating furniture range

Dimensions (mm)	1100(h) x 525(d) x 420(w)	
Capacity (L)	80	
Materials	Steel	
Finish options	Powder coated steel options	
Extra features	Optional ash & gum tray	

Dimensions (mm)	793(h) x 558(ø) / 859(h) x 630(ø)
Capacity (L)	40 / 85 / 110
Materials	Satin polished stainless steel
Extra features	40 Litre option available as flat top or flared top.

Dimensions (mm)	1075(h) x 560(ø)
Capacity (L)	85
Materials	Medium Density Polyethylene
Finish options	Range of colours
Extra features	Refuse sack holder and ballast cartridge available as extra

NATURAL ELEMENTS®



PEDRETA



PEGASO



Dimensions (mm)	1040 (h) 600(d) x 480(w)
Capacity (L)	90
Materials	Steel and timber
Finish options	Two timber options available
Extra features	Ash tray Double aperture

Dimensions (mm)	820(h) x 750(d) x 600(w)
Capacity (L)	50
Materials	Acid-etched cast stone
Finish options	Various colours available

Dimensions (mm)	H 1200
Capacity (L)	104
Materials	Precious stone aggregates
Finish options	Various colours available
Extra features	Hood and ash tray available

Dimensions (mm)	1170(h) x 680(ø)
Capacity (L)	130
Materials	Medium Density Polyethylene
Finish options	A range of RAL colour options
Extra features	Ashtray and gold bands available

PIONEER

DETER

PLAZA



Dimensions (mm)	760(h) x 600(d) x 380(w)
Capacity (L)	120
Materials	Powder coated steel & Iroko timber
Finish options	Powder coated
Extra features	Co-ordinating furniture

REGENT

nensions (mm)	525(h) x 390(w)/ 645(h) x 425(w)	
oacity (L)	30/50	
terials	Medium Density Polyethylene	
ish options	Range of colours	
ra features	Dog litter bin option	

RENDEZVOUS



Dimensions (mm)	820(h) x 490(ø)
Capacity (L)	55
Materials	Cast Iron and hardwood
Finish options	Timber finish options
Extra features	Surface or ground fixed



SOCRATES

Dimensions (mm)	460 (h)/ 700 (h)
Capacity (L)	30
Materials	Acid-etched cast stone
Finish options	Two colour options
Extra features	Two sizes

SPRING





STRADA



STRATIC



WATERSIDE

Dimensions (mm)	969(h) x 550(d) x 550(w)
Capacity (L)	60
Materials	Concrete
Finish options	Two colour options
Extra features	Co-ordinating furniture range


Dimensions (mm)	1000(h) x 500(ø)
Capacity (L)	43
Materials	Concrete
Finish options	Exposed silver grey
Extra features	Open top, rain shield, wire metal basket, polythene liner available

Dimensions (mm)	1100(h) 500(d) x 450(w)
Capacity (L)	85
Materials	Stainless steel and timber
Finish options	Two colourways
Extra features	Mixed recycling option


Dimensions (mm)	1015(h) x 450(d) x 850(w)
Capacity (L)	130
Materials	Ferrocast®
Finish options	A range of colour options
Extra features	Single aperture








YARG




CARMEL

		1					I
Dimensions (mm)	1452(ø)		Dimensions (mm)	1800(w) x 800(d)		Dimensions (mm)	From 1000 x1000 to 1600 x 1600 (square)
Control on out we (no no)	400(~)		Central aperture (mm)	710(w) x 330(d)			960mm to 360mm ø (circular)
Central aperture (mm)	400(ø)		Materials	rials Cast aluminium and	Cen	Central aperture (mm)	From 530 (ø) to 1360 (ø)
Materials Ultratense Concrete (UTC)		galva	galvanised steel			(
Materials	ottraterise concrete (orc)		Finish options	Forge black as standard		Materials	Cast aluminium (circular) Cast stone surround (square)
Finish options	Two colour options		Extra features	Embedded at paving level		Finish options	Zinc plated & oxidized (circular) Acid etched (square)

ICARIA



Dimensions (mm)	120(w) x 120(d)
Central aperture (mm)	550 (ø)
Materials	Acid-etched cast stone
Finish options	Two colour options
Extra features	Bevelled to aid irrigation Embedded at paving level



Marshalls Creating Better Spaces

	10 m

CAST IRON 58 SERIES



CAST IRON 60 SERIES

CAST IRON 61 SERIES

CAST IRON 63 SERIES

CAST IRON 64 SERIES

CAST IRON 65 SERIES

CAST IRON 66 SERIES





























Dimensions (mm)	700, 1000, 1200, 1400, 1800
Central aperture (mm)	700, 1000 & 1200 (400ø), 1400 & 1800 (600ø)
Materials	Cast iron
Finish	Black RAL 9005

Dimensions (mm)	1000, 1200
Central aperture (mm)	600ø
Materials	Cast iron
Finish	Black RAL 9005

Dimensions (mm)	1000, 1200, 1400
Central aperture (mm)	1000 & 1200 (400ø), 1400 (600ø)
Materials	Cast iron
Finish	Black RAL 9005

Dimensions (mm)	1000, 1200, 1400
Central aperture (mm)	1000 & 1200 (400ø), 1400 (600ø)
Materials	Cast iron
Finish	Black RAL 9005


Dimensions (mm)	1200, 1400
Central aperture (mm)	1200 (400ø), 1400 (600ø)
Materials	Cast iron
Finish	Black RAL 9005

Dimensions (mm)	1200, 1400
Central aperture (mm)	1200 (400ø), 1400 (600ø)
Materials	Cast iron
Finish	Black RAL 9005

Dimensions (mm)	1000, 1200, 1400
Central aperture (mm)	1000 & 1200 (400ø), 1400 (600ø)
Materials	Cast iron
Finish	Black RAL 9005

Dimensions (mm)	1000, 1200, 1400	
Central aperture (mm)	1000 & 1200 (400ø), 1400 (600ø)	
Materials	Cast iron	
Finish	Black RAL 9005	

FERROCAST® PARK LANE



Dimensions (mm) | 1000, 1200, 1400, 1800


700,1000 & 1200 (400ø)

1400 & 1800 (600ø)

Ferrocast® polyurethane

Black RAL 9005

FERROCAST® 58P SERIES



Dimensions (mm) 700, 1000, 1200, 1400

Finish

(600ø)

Ferrocast®


Black RAL 9005

700,1000 & 1200

(400ø), 1400 & 1800



FERROCAST® 59P SERIES



Dimensions (mm) | 1000, 1200, 1400

Central aperture | 1000 & 1200 (400ø),


1400 (600ø)

Ferrocast® polyurethane


Black RAL 9005



FERROCAST® 61P SERIES











Dimensions (mm)	1000, 1200, 1400
Central aperture (mm)	1000 & 1200 (400ø), 1400 (600ø)
Materials	Ferrocast® polyurethane
Finish	Plack DAL OOOE

FERROCAST® 65P SERIES






FERROCAST® 66P SERIES





FERROCAST® 68P SERIES

Marshalls
Creating Better Spaces





Dimensions (mm)	1000, 1200, 1400	Dimensions (mm)	1000, 1200, 1400	Dimensions (mm)	1000, 1200, 1400
Central aperture (mm)	1000 & 1200 (400ø), 1400 (600ø)	Central aperture (mm)	1000 & 1200 (400ø), 1400 (600ø)	Central aperture (mm)	1000 & 1200 (400ø), 1400 (600ø)
Materials	Ferrocast® polyurethane	Materials	Ferrocast® polyurethane	Materials	Ferrocast® polyurethane
Finish	Black RAL 9005	Finish	Black RAL 9005	Finish	Black RAL 9005



STEEL PEBBLES (ROUND)

STEEL PEBBLES (SQUARE)

STEEL ROOTS (ROUND)

STEEL ROOTS (SQUARE)

STEEL STARS (ROUND)

STEEL STARS (SQUARE)

STEEL WAVES (ROUND)

STEEL WAVES (SQUARE)

















Dimensions (mm)	1200,1500, 1800
Central aperture (mm)	600ø
Materials	Steel
Finish	Sand textured powder coated brown 650

Dimensions (mm)	1200,1500, 1800
Central aperture (mm)	600ø
Materials	Steel
Finish	Sand textured powder coated brown 650

mensions (mm)	1200,1500, 1800	Di
entral aperture (mm)	600ø	Ce
aterials	Steel	Ma
nish	Sand textured powder coated brown 650	Fir

Dimensions (mm)	1200,1500, 1800
Central aperture (mm)	600ø
Materials	Steel
Finish	Sand textured powder coated brown 650

Dimensions (mm)	1200,1500, 1800
Central aperture (mm)	600ø
Materials	Steel
Finish	Sand textured powder coated brown 650

Dimensions (mm)	1200,1500, 1800
Central aperture (mm)	600ø
Materials	Steel
Finish	Sand textured powder coated brown 650

Dimensions (mm)	1200,1500, 1800	Dimensions (mm)
Central aperture (mm)	600ø	Central aperture (mm
Materials	Steel	Materials
Finish	Sand textured powder coated brown 650	Finish

Dimensions (mm)	1200,1500, 1800
Central aperture (mm)	600ø
Materials	Steel
Finish	Sand textured powder coated brown 650

Post & Rail

Marshalls Landscape Protection offers a range of post and rail systems which are available in a range of styles and materials.

Marshalls has created a wealth of experience in specialist post & rail systems. The materials used to create these systems vary from steel to stainless steel and Ferrocast[®], the modern alternative to cast iron. Steel and Stainless Steel is usually found in city centres, junctions and in crowded places with high traffic. Ferrocast® systems are suited to all environments and are used mostly for seaside surroundings, as the material will not rust or corrode.

The objectives of a pedestrian post & rail system is to sustain specified design loadings while blending with the environment, increasing the safety of pedestrians and other non-vehicular highway users and matching the architectural surroundings.

Our design team can work closely with specifiers and architects. Where necessary we can design solutions to BS EN 7818.

By choosing Marshalls for your Post & Rail systems, you acquire:

- Experienced internal and external specialists to assist you with specifying your design, the materials and any budgetary requirements
- An expert project engineer who can talk you through any installation queries
- An inhouse project management team, dealing with your design whether simple or complicated – offering peace of mind and ease of design creation
- An in-house installation team, a professional cost effective solution to ensure a high standard of finish

Offering a wide range of material options and designs alongside our standard solutions and being specialists in bringing custom designs to life, Marshalls is the ideal partner to choose for any great post & rail scheme that needs to be created.

GEO BALUSTRADE



Height (mm)	1096 / 1106	
Rail diameter (mm)	48.3	
Post diameter (mm)	76	
Std fixing type	Root fixed / Surface Mounted	Horizontal
Panel Width Options	Horizontal: 1000, 1500, 2000 Vertical: 1000, 1500, 2000 * can be done as custom widths to suit	
Infill options	Horizontal / Vertical	Vertical

GEO HANDRAIL & BALUSTRADE





Height (mm)	1096/1106
Rail diameter (mm)	76
Std fixing type	Root fixed / Surface Mounted
Panel Width Options	Horizontal: 1000, 1500, 2000 Vertical: 1000, 1500, 2000
Rail options	Horizontal Vertical



Height (mm)	1201	RAL colour (F	estival only)	
Rail diameter (mm)	48			
Std fixing type	Surface Mounted	RAL 9005	RAL 9010	R.A
Material	Steel (Festival) or Stainless Steel (M3)			
Rail options	Steel or stainless steel	RAL 5010	RAL 6005	R/

Post & Rail: Ferrocast®



Height (mm)	1200	RAL colours a
Rail diameter (mm)	50	RAL 9005
Std fixing type	Surface Mounted	NAL 9003
Rail options	3 Rail 4 Rail 5 Rail 6 Rail	RAL 5010



Height (mm)	900/700
Rail diameter (mm)	50
rian diameter (min)	
Std fixing type	Root fixed
Rail options	2 Rail (h900mm)
	1 Rail (h700mm)

Height (mm)	1045
Rail diameter (mm)	50
Std fixing type	Surface Mounted
Rail options	n/a







SEAHAM

Height (mm)	1139 (2&3 Rail) 1407 (4 Rail)
Rail diameter (mm)	50
Std fixing type	Root fixed Surface Mounted
Rail options	2 Rail 3 Rail 4 Rail

Height (mm)	1273 (2 Rail) 1269 (3 Rail)	
Rail diameter (mm)	50	
Std fixing type	1269 (3 Rail)	
Rail options		

Height (mm)	1226
Rail diameter (mm)	50
Std fixing type	Root fixed Surface Mounted
Rail options	3 Rail

Post & Panel



Height (mm)	1000 / 1003/ 1020
Rail diameter (mm)	50
Std fixing type	Root Fixed/Surface Mounted
Panel width (mm)	2000 / 1500 / 1000
Hi-Vis infill options	HV2 / HV4 / HV8
Post diameter (mm)	88.9/ 114.3


















Other styles available

Chelsea is

Chelsea CUSTOM POST AND RAIL






Material

1000 (Handrail) Height (mm) 1100 (Balustrade) Rail diameter (mm) Std fixing type Surface Mounted Panel Width Options Various 316 Stainless steel, mild steel and

Corten powder

effect





TRAFFIC CALMING

Marshalls' range of traffic calming systems are designed to improve environments for vehicular and pedestrian traffic through proactive traffic management.

Designed to improve the liveability of trafficked environments, Marshalls' products provide a safe and secure traffic management solution for all users.

Marshalls' traffic calming products are aesthetically pleasing and proven in use for a variety of applications ranging from homezones and adoptable estate roads to highways, either new or existing.

The accurate preformed shapes and profiles of Marshalls traffic management products, produced by quality controlled manufacturing processes, ensure compliance to standard.

Legislation

- All products illustrated are designed to be installed in the highway giving due regard to the appropriate legislation and standards.
- 1999 No 1025: Highways, England and Wales. The Highways (Road Hump) Regulations 1999.
- 1999 No 1026: Highways, England and Wales. The Highways (Traffic Calming) Regulations 2000.





Traffic Calming

SPEED CUSHIONS

REINFORCED CONCRETE CUSHIONS

Marshalls offers two Speed Cushion designs to reduce speeds of traffic with differing characteristics to different levels. The cushions comply with the Traffic Advisory Leaflet issued by the DfT, October 1994.

One piece structural units are designed to withstand all traffic loadings whilst easy installation and low maintenance reduces whole life costings.

Dimensional accuracy ensures compliance to design standard and coloured concrete contrasts with road surface increasing visibility to road users.

PLATEAU SPEED CUSHION

- A reinforced concrete cushion with a plateau top of 70mm
- A range of widths are available
- Approach/exit ramp of 1:8:6 and side slope of 1:4:3
- Available in red as standard, other colours can be made to order

DOMED

- A reinforced concrete cushion with a dome of 65mm high
- A more suitable solution than the Plateau for areas with numerous bus movements



PLATEAU SPEED CUSHION PLATEAU SPEED CUSHION — 1000/1150/1300 — → → 300 → DOMED SPEED CUSHION DOMED SPEED CUSHION


SPEED CUSHIONS 4 AND 6 PIECE RUBBER PLATEAU CUSHIONS

Marshalls' Rubber Speed Cushions feature a unique modular design allowing fast installation on any road surface with standard tools.


They have been designed to meet and exceed global safety standards while allowing emergency vehicles to pass quickly without delay.

Our range of Rubber Speed Cushions offer instant traffic calming results and can be removed during road works and even reused on alternate routes.

- 4 and 6 Piece Cushions available
- 4 Piece: 2 right angles, 2 left angles
- 6 Piece: 2 right angles, 2 left angles, 2 middles sections
- Easy to install or remove
- Includes zinc plated steel bolts and washers
- Factory fitted reflective strips for increased visibility
- Fixed together using T-connectors, 7 for the 6 piece and 4 for the 4 piece







S RAMP PRE-CAST REINFORCED CONCRETE ROAD HUMP



S-Ramp is a pre-formed segmental sinusoidal profiled ramp system which enables road humps or table tops of 75mm high to be constructed.

Units can be laid kerb-to-kerb using standard pieces only. Alternatively a freestanding table can be achieved by the inclusion of corner and side units.



*Natural products are manufactured from aggregates sourced locally to the works and contain no pigmentation, therefore colour variation between products from different works is possible.

Traffic Calming

SPEED CHECK CONCRETE ROAD HUMP



A unique product which acts as a restraint and starter block for 1:10 ramp slopes to be constructed in block paving; however, ramps of 1:15 can also be constructed. Shape, size and finish complements concrete block paving, although other materials can be used.


TRAFFIC RAMPS PRE-CAST REINFORCED CONCRETE ROAD HUMP



Traffic ramps are reinforced pre-cast concrete ramp units that form part of a road hump installation.

The central plateau section of the road hump can be constructed from material to suit the application from concrete block paving to black top.

The substantial size and weight of the units ensure suitability in locations such as arterial routes, where traffic is heavy and faster moving.





Kerb Systems

Titan® Containment Kerb Radius



oth	Grey	
-----	------	--

	External Radius										Internal Radius				
Height (mm)	400	400	400	400	400	400	400	400	400	400	400	400	400	400	
Face Length (mm)	965/975	955/975	945/975	935/975	797/841	734/785	807/884	317/394	217/294	975/955	975/935	836/785	961/884	589/666	
Width (mm)	390	390	390	390	390	390	390	390	390	390	390	390	390	390	
Radius Covered (m)	76/25	25/15	15/11	11/8.5	7.5	6.0	4.5	2.0	1.5	76/25	76/25	76/25	76/25	76/25	
No per 1/4 circle	122-40	40-24	24-18	18-14	14	12	8	8	8	122-40	122-40	122-40	122-40	122-40	
Weight (kg)	233	232	230	229	207	194	221	104	80	232	229	182	198	132	





Titan® Quadrants



	Straight	Straight	Straight	Straight	Straight	Large Transition Left Hand	Small Transition Left Hand	Large Transition Right Hand	Small Transition Right Hand
Profile	Titan®	Titan®	Titan®	Titan®	Titan®	Titan® to Half Battered	Titan® to Half Battered	Titan® to Half Battered	Titan® to Half Battered
Height (mm)	400	400	400	400	400	400/310	310/220	400/310	310/220
Face Length (mm)	1000	1000	665	495	325	1000	1000	1000	1000
Width (mm)	390	390	390	390	390	390/264	264/137	390/264	264/137
Weight (kg)	76/25	76/25	25/15	15/11	11/8.5	210	130	210	130

Kerb Systems

Bus Stop Kerb





Smooth Grey

	Kerb	Channel	Kerb Radius Unit	200 Drop Kerb Left Hand	200 Drop Kerb Right Hand	180 Drop Kerb Right Hand	180 Drop Kerb Left Hand	160 Drop Kerb Left Hand	160 Drop Kerb Right Hand
Height (mm)	380	180	380	380	380	360	360	340	340
Face Length (mm)	1000	1000	250	1000	1000	734	734	472	472
Width (mm)	100/240	350/385	240	245	245	228	228	125	125
Weight (kg)	145	120	145	110	110	100	100	90	90
No. Required	-	-	9	9	12	14	18-14	24-18	40-24



PROJECT SUMMARY

Fosse Shopping Park is one of Britain's biggest out of town shopping parks, situated on the Southern edge of Leicester. The 265,000 sq. ft. shopping centre was built in 1989 and is home to a number of recognised high street shops and

Having not done so for a number of years, Fosse Shopping Park was looking to give its external areas a modern refurbish. They recognised the need to invest in updated perimeter protection and landscape furniture.












Marshalls



Marshalls

PROJECT SUMMARY

The threat of flooding is increasingly linked to climate change and increasing urbanisation. Leeds narrowly escaped a major flood during the 2007 floods and since then there have been several localised flood events closing the train station, blocking roads and resulting in city centre residents being evacuated from waterfront properties.

In order to protect businesses, homes, the transportation network and the city economy in the future, Leeds City Council needs to provide flood defences. A flood alleviation scheme (FAS) has been designed to protect the city centre from a 1:75-year flood, and the planned project will involve the construction of flood defence interventions between Leeds train station and Knostrop Lock downstream of the city centre.









PROJECT SOLUTION A key aim of the project has been to identify and build in sustainable construction techniques. Early in the construction phase, BMMJV identified a cost, programme and environmentally beneficial alternative to the proposed hand railing solution. The contract required BMMJV to remove several types of existing cast iron and timber handrails and to replace on a 'like for like' basis. However, it was pointed out by the site team that once the existing railings had been removed, there would be no railings left to match and it would not enhance the built environment if identical railings were adopted along the defences. The site management team convinced planners to adopt this principle and to use the same type of railings throughout. Having agreed this, BMMJV and Marshalls, supported by the Leeds City Council design team and Arup, investigated the substitution of the cast steel railings with Ferrocast® railing posts which was put to and accepted by the council's planning department. Ferrocast® is a polyurethane mix of an engineering grade specification which was developed from its use in the mining, quarrying and North Sea Oil Industries. These harsh environments were perfect testing conditions to prove that it would be an ideal material for manufacturing street furniture that would withstand the rigours of the urban environment. The durability of Ferrocast® makes it the preferred material when manufacturing post and rail for developments such as the Leeds Flood Alleviation Scheme It has a longer, maintenance-free lifespan and helps to reduce ongoing maintenance costs.

ः

Marshalls

of the art showroom in Preston, Lancashire. The new showroom provides a timeless, modern and












Jaguar Land Rover recently opened their brand new, state

contemporary environment; perfect for visitors to experience their cars in sophisticated surroundings. Jaguar Land Rover were looking for a simple yet stylish and secure method of protecting their premises and vehicles.



BESPOKE SEATING



PROJECT SUMMARY

As part of a £3bn redevelopment programme in Elephant and Castle, the area is being transformed into an exciting new destination for London over the next 15 years. The regeneration includes transforming the wasted space in Elephant and Castle into a usable, thriving public space, including a pedestrianised town centre, market square, and new green spaces. Local people will benefit from the dramatically improved physical environment with tree-lined streets, high quality open spaces and a largely traffic-free environment, allowing more space for social seating, popup markets and events.









PROJECT:

Exhibition Road

PAVING, SEATING, BESPOKE LIGHTING



PROJECT SUMMARY

The RIBA Award winning £28million redevelopment of Exhibition Road has transformed one of London's most visited streets into one of the most accessible cultural destinations in the world.

It is one of London's most high profile streets, being home to leading cultural and academic institutions such as the Natural History Museum and Imperial College, but over time had become inefficient, being dominated by traffic with narrow, crowded pavements and street clutter, and was unable to handle the millions of people who visit every year. A complete redesign was needed to improve infrastructure and access to facilities.

The Royal Borough of Kensington & Chelsea decided to run a design competition for the space, which was won by Architects Dixon Jones.

The winning design's vision was a complete overhaul of the street, creating a 'shared space', which means that pedestrians and vehicles co-exist without one being the dominant force. This is created by the removal of kerbs, pavements and other obstructions, this encourages motorists to slow down and engage with the pedestrians creating a safer and more secure environment for all.

Marshalls was approached to supply a range of key physical features of the redevelopment; natural stone, bespoke street lighting, drainage solutions and landscape furniture.







PROJECT SOLUTION

The finished result makes Exhibition Road one of the most striking thoroughfares in London. The paving's diamond shape pattern, as well as being visually appealing, naturally leads users across the street from one famous cultural centre to another.

The clutter free environment feels calm, and allows crowds to flow more freely over the paving allowing for easy passage from South Kensington tube station to the museums which line the famous road.

The bespoke lighting masts enhance the appearance of the streetscape's many colours, textures and finishes, and give pedestrians the feeling of added security.

PROJECT SUMMARY

In May 2012, in advance of the Olympics and Diamond Jubilee celebrations, Leicester Square reopened following major public realm improvements to this world famous London square. A flagship scheme in the Mayor's Great Outdoors programme, the design was undertaken by Burns + Nice for Westminster City Council specifically for Leicester Square. The aim of the scheme was to re-establish Leicester Square and its Gardens as a 'must see' destination and to create a distinct sense of place in London's West End.

The Square's distinctive new design features granite paving, bespoke lighting, signage, extensive seating (both formal and informal), stainless steel railings and gates, and a new water feature.

Marshalls manufactured the bespoke seats and benches, which are located in the Gardens. The unique seating comprises a polished bronze frame and Iroko timber slats, providing a premium quality product of a timeless design that is also robust. Engineers at Marshalls collaborated closely with Burns + Nice in order to deliver an exceptional result, entirely in line with the designer's original intent. The seats and benches are designed in a modular configuration, defined by the new central area within the Gardens.

Particular challenges overcome included the manufacture of the timber slats, that were cut to a radius in two dimensions, the manufacture of the bronze frame, accommodating level changes across the site and installation on site that required the paving pattern to be respected.







PROJECT:


Alhambra Theatre

BESPOKE SEATING



PROJECT SUMMARY

As part of a regeneration scheme to modernise the exterior space outside of the Alhambra Theatre in Bradford, the client wanted to create an inviting yet contemporary area which encouraged passers-by to sit and enjoy the surrounding area.









PROJECT SUMMARY

The client BAM Construction was seeking a solution to protect the glass frontage of the shops and restaurants located at this leisure park. A depth restriction of 200mm was placed on any installed products.

The client was seeking protective products which complemented the modern surroundings of the leisure

The client also required a range of other street furniture products, such as cycle and motorcycle stands.







CASE STUDY PROJECT:

Leisure Plaza Milton Keynes

ः

Marshalls

BOLLARDS

PROJECT:

PROJECT SUMMARY

The client Land Securities completed a large outlet village in the South East of England. As a key part of the public realm section of the project, the client sought protective street furniture solutions which would not only offer the required level of protection but would also complement the surroundings of the shopping centre.

The client approached Marshalls to seek advice on what solutions would work best bearing in mind that the development sits on top of a major road tunnel and therefore only products which require shallow installation would be appropriate.

The client was also seeking solutions which would suit the modern aesthetic of the development and which would enhance the surroundings.











Marshalls







Creating Better Spaces

Registered Office: Marshalls plc, Landscape House, Premier Way, Lowfields Business Park, Elland, HX5 9HT United Kingdom

UK: 0370 600 2425

International: +44 (0) 1422 312 993 USA: +1 603 465 1254 UAE: +971 50777 6308 marshalls.co.uk/commercial/ landscape-protection